U. S. DEPARTMENT OF AGRICULTURE

FOREST SERVICE

FIELD NOTES

HOMESTEAD ENTRY SURVEY NO. 627

SITUATED IN THE CROOK NATIONAL FOREST

ADMINISTRATIVE DISTRICT NO. 3

In Section 7 , un-surveyed, Township 11 S., Range 25 E. In Section 8 , un-surveyed, Township 11 S., Range 25 E.

of the

Gila and Salt River Base & Meridian.

State of Arizona.

Applicant for listing N. A. Rose,

Residence

Wilcox, Ariz.

Application No. 139

, dated February 25

. 19 10%

List No. 3-1724

, dated

January 30

. 19 12

Applicant for survey Mark A. Cook

Residence

Wilcox, Arizona.

H. E. No. 032342 , dated February 23 , 19 17

Land Office

Phoenix, Ariznna.

Survey executed by Thomas F. Myers, - Surveyor, Forest Service.

[Forest Service Title.]

Under special instructions dated July 21

, 19 226

Survey commenced May 23

, 19 23.

Survey completed

May 23

, 19 23.

Under Acts of June 11, 1906, and May 11, 1922.

[OVER]

OATH OF ASSISTANTS

We hereby certify that we assisted

Surveyor - Forest Service

[Forest Service Title.]

Thomas F. Myers,
in surveying all those

parts or portions of Homestead Entry Survey No. 627 , in the State of Arizona which are represented in the following field notes as having been surveyed by him and under his direction; and that said survey has been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the corner monuments established, according to the instructions furnished by the United States Surveyor General for Arizona.

Note: It would have been very expensive and inconvenient to appear before an officer to administer Oaths to Assistants; hence they were taken by the Surveyor.

Geow Cook

Chainman.

Subscribed and sworn to before me this

23rd

day of

Max

., 19 23.

Surveyor - Forest Service.

OATH OF SURVEYOR

I, Thomas F. Myers, Surveyor - Forest Service, [Forest Service Title.]

do solemnly swear that, in strict conformity with the special instructions of the United States Surveyor General for Arizona, dated July 21, 1922, and the laws of the United States, I have well, faithfully, and truly, in my own proper person, surveyed a tract of land embraced in

List , No. 3-1724 , dated January 30, 19 12 , for Patent , under the Act of June 11 , 19 06 , the same to be known as Homestead Entry Survey No. 627 , situated within the Crook National Forest, in un-surveyed Section 7 , Township 00 11 S. Range 25 E. , and un-surveyed Section 8 , Township 11 S. Range 25 E. ,

of the Gila & Salt River Base and meridian, Arizona, and the related retracements and resurveys and section subdivisions, which are represented in the following field notes as having been surveyed by me; and I further solemnly swear that all the corners of said survey have been established and perpetuated in strict accordance with the stated special instructions, and in the specific manner described in the field notes, and that the following are the original field notes of such

Thomas & myers

Surveyor - Forest Service.
[Forest Service Title.]

Subscribed and sworn to before me this

13th

day of

November

, 19 23.

Exhel & Myers Notary Public.

SEAL.

LL3 V

8-2349

My commission expires April 12, 1925.

CROOK NATIONAL FOREST

STATE OF ARIZONA

1.

Chains

Applicant for listing, N. A. Rose; Application No. 139, dated February 25, 1910; List No. 3-1724, dated January 30, 1912; H. E. 032342, made in the Phoenix Land Office on February 23, 1917, by Mark A. Cook. Surveyed under special instructions from the Surveyor General for Arizona, dated July 21, 1922, and designated as Homestead Entry Survey No. 627.

Situated in what will probably be when surveyed Secs. 7 and 8, T. 11 S., R. 25 E., Gila and Salt River Base and Meridian, Crook National Forest, Arizona.

Surveyed under the Acts of June 11, 1906, and May 11, 1922.

Survey commenced May 23, 1923, and executed with a Buff and Buff transit No. 14631, equipped with Smith solar attachment.

. T'eo'RO & . Li . Lanc

I test the adjustments of the transit and make necessary corrections.

All distances are horizontal, and were reduced from measurements made directly on the slope with a 400 link steel tape. The slope angles were determined with a clinometer.

May 23, 1923.

At my station near Cor. No. 2 of this survey in Lat.

32°29'34" N., Long. 109°49'23" W. from Forest Service

Base Map, at 6h. 34m. 56s. p.m. 1.m.t., I observe

Polaris with telescope direct, reading an angle of

0°51' from star to right to reference mark, a stake

driven in the ground 10 chs. northwardly of station.

Greenwich m.t. U. C. Polaris, May 23, 9h 33.1m a.m.

Corr for Long.

1.2

1.m.t. U. C. Polaris, May 23, 1923, 9h 31.9m a.m.

1.m.t. Obsn. Polaris, May 23, 1923, 6h 34.9m p.m.

Hour angle 9h 03. m

2.

CROOK NATIONAL FOREST

STATE OF ARIZONA

Chains

Azimuth of Polaris 0°54.3'00" W.

Bearing of Reference Mark N.0°03.3' W.

At same station at 7h. 09m. 12s. p.m. 1.m.t., I again observe Polaris with telescope reversed, reading an angle of 0°47'30" from star to right to same reference mark.

1.m.t. U. C. Polaris, May 23,1923, 9h 31.9m a.m.
1.m.t. obsn. Polaris, May 23, 1923, 6h 50.2m p.m.
Hour angle 9h 18.3m

Azimuth of Polaris 0°50.5' W.

Bearing of Reference mark N.0°03.0' W.

The bearing of reference mark as determined from the mean of the two obsns. is N. 0°03'09" W. I accept mean bearing of reference mark as N. 0°03' W., and from the corresponding meridian all courses of this survey were deflected by sustained angulation.

May 23, 1923.

BOUNDARIES OF CLAIM

May 24, 1923.

Beginning at Cor. No. 1.

Deposit a granite stone 4x5x8 ins., 20 ins. in ground, marked with a +, over which set a granite stone 30x12x 12 ins., chiseled + on top and 1 HES 627 on SE. face; raise a mound of stone 3 ft. base, 2 ft. high SE. of Cor.

No witnesses available, pits impracticable.

Cor. H/4 of the list survey, a granite stone

14x9x30 ins. above ground, marked, and witnessed as described by the Forest Service,

bears S. 82°00' W. 174 lks. I destroy all

trace of this list Cor.

The 1/4 Cor. between Secs. 7 and 12, T. 11 S., Rs. 24 and 25 E., an iron post 1 in. dia.

10 ins. above ground, with brass cap, marked

. 3.

CROOK NATIONAL FOREST

STATE OF ARIZONA

Chains

11.00

22.60

and witnessed as described by the Surveyor General, bears S. 88°51' W. 60.49 chs. by direct measurement.

Lat. 32°29'34" N., Long. 109°49'45" W. from Forest Service Base Map.

Mag. decl. at 8 a.m. is 14°05' E., mean mag. decl.

Thence S. 89°31' E.

Over rolling mesa land through scattering mesquite.

3.99 Wash 12 1ks. wide, 1 ft. deep, course South.

Wash 300 lks. wide, 5 ft. deep, course SW.

Fence bears NW. and SE.

30.22 To Cor. No. 2.

Identical with Cor. H/l of the list survey, a grey granite stone 8x5x12 ins. above ground, marked and witnessed as described by the Forest Service. I destroy all trace of this list Cor.

Deposit blue granite 3x6x8 ins. 14 ins. in ground, marked with a +, over which set grey granite stone 24x10x10 ins., chiseled + for the point and 2 HES 627 on Sw. face; dig pits 18x18x12 ins. crosswise on this and succeeding course 3-1/2 ft. distant and raise a mound of stone 3 ft. base 1-1/2 ft. high Sw. of Cor., whence:

A black walnut 11 ins. dia. brs. S. 10°35' E.

418 1ks., blazed and scribed 2 HES 627 + BT.

No witnesses available.

Thence S. 0°46' E.

Descend 20 ft. over rocky S. slope through scattering mesquite.

Arroyo in Hayes Canyon 45 lks. wide, 4 ft. deep, course WSW., thence across sandy bed of canyon.

Arroyo 20 lks. wide, 2 ft. deep, course SW. Bottom of descent. Ascend 12 ft. over NW. slope through

4.42

8.22

HOMESTEAD ENTRY SURVEY NO. 627

CROOK NATIONAL FOREST

4.

STATE OF ARIZONA

Chains	scattering mesquite.											
8.81 8.90 10.30	Fence bears NE. and SW. Trail bears NE. and SW: To Cor. No. 3.											
Ü	Identical with for. H/2 of List survey, a grey granite											
	stone 10x5x6 ins. above ground, marked and witnessed											
	as described by the Forest Service. I destroy all											
	trace of this list Cor.											
	Deposit a porphyry stone 5x8x10 ins. 24 ins. in ground,											
.07	marked with a + over which set a porphyry stone 28x10x											
	12 ins., chiseled + on top and 3 HES 627 on NW. face;											
	raise mound of stone 2 ft. base 1-1/2 ft. high NW. of											
	Cor., whence:											
	A black walnut 14 ins. dia. brs. N. 68°40' W.											
	278 lks., blazed and scribed 2 HES 627 + BT.											
	Thence N. 89° 34' W.											
	Over gently rolling land.											
.55	Trail bears NE. and SW.											
1.65	Fence bears NE. and SW.											
2.05	Fence bears N. and S.											
2.75	Left bank of arroyo in Hayes Canyon, 6 ft. deep, bears											
	SW. Thence down sandy bed of arroyo.											
3.30	Trail bears NW. and SE.											
3.90	Left bank of same arroyo, bears NW.											
	Thence across foot of rocky N. slope											
6.00	Fence bears N. and S. Thence over bottom land.											
7.80	Left bank same arroyo from ENE. Course W., thence down											
	sandy bed of arroyo.											
11.20	Left bank of same arroyo from E. Course NW.											
15.75	Middle of same arroyo in Hayes Canyon, 50 lks. wide, 3											
	ft. deep, course SW.											
16.30	Road bears NE. and SW.											
18.40	Middle same arroyo, 50 lks. wide, 3 ft. deep from ESE.											
18.50	Course NW. Road bears N. 60°00' W. and S. 60°00' E. Road bears SW. and NE.											

Action in	Chains	Fence bears NW. and SE.										
	29.59	Middle of arroyo in Hayes Canyon 60 lks. wide, 3 ft.										
	20.00											
	30.24	deep, course SW. To Cor. No. 4.										
	00.24											
C. Na.		Deposit a granite stone 2x8x10 ins. 24 ins. in ground,										
101		marked with a + over which set a sandstone 30x24x12 ins										
		chiseled + on top and 4 HES 627 on NE. face; raise a										
1000		mound of stone 2 ft. base 1-1/2 ft. high NE. of Cor.,										
		whence:										
	.2	A black oak 18 ins. dia. brs. S. 46°20' W.										
		121 lks.										
		A black walnut 20 ins. dia. brs. N. 70°55' E.										
		226 lks.										
		Each blazed and scribed 4 HES 627 + BT.										
		Cor. H/3 of the list survey, a grey granite										
		stone 12x24x18 ins. above ground in forks										
		of desert willow tree, marked and witnessed										
		as described by the Forest Service, bears										
		S. 6°00' W. 12 lks. dist. I destroy all										
		trace of this list survey.										
		Thence N. 0°46' W.										
		Over level bottom land.										
	2.00	Begin ascent of 20 ft.										
	5.04	Top of ascent, thence over level mesa land through										
		scattering mesquite.										
	10.30	To Cor. No. 1, the place of beginning.										
		AREA										
		Total area 31.13 acres.										
1												

IMPROVEMENTS

The improvements made upon and for the benefit of this claim and belonging to the claimant consist of the

STATE OF ARIZONA

Chains	following:
	An adobe shed 14x60 ft., the long sides extending
	E. and W., the SE. Cor. of which bears N. 54°
	46' W. 13.95 chs. from Cor. No. 3.
4	Value \$100.00
, 20, 200	A frame barn 20x32 ft., the long sides extending
did als	E. and W., the SE. Cor. of which bears N. 58°
8.9	17' W. 14.18 chs. from Cor. No. 3.
	Value\$200.00
	Center of cement tank 30 ft. dia. 3 ft. deep,
	bears S. 56°54' W. 11.35 chs. from Cor. No. 2.
	Value \$300.00
	2 pole corrals, each of which are about 60 ft.
	diameter. The cement tank above described
	is located between the two corrals, one of
	which bears NW. and the other SE. from the
	tank.
	Value \$100.00
	· A dug well 50 ft. deep, with windmill, gas
	engine and galvanized iron tank 12 ft.
	diameter, 10 ft. high, over well. The center
	of windmill bears N. 83°34' W. 9.83 chs.
	from Cor. No. 3.
	Value \$600.00
	A dug well 30 ft. deep with windmill and gas
3	engine over well; the center of windmill bears
	N. 71°21' W. 10.75'chs. from Cor. No. 3.
	Value
	An adobe dwelling 40x38 ft., the long sides
	extending N. and S., the NE. Cor. of which
	bears N. 79°09' W. 11.39 chs. from Cor. No. 3.
	Value \$1000.00
	An adobe store house 10x12 ft., the long sides
	extending N. and S., the NE. Cor. of which
	bears N. 80°04' W. 10.89 chs. from Cor. No. 3.
	Value \$ 50.00

HOMESTEAD ENTRY SURVEY NO. 627

CROOK NATIONAL FOREST

STATE OF ARIZONA

7.

Chains

A frame and adobe house 12x24 ft., the long sides extending E. and W., the NE. Cor. of which bears N. 76°36' W. 10.13 chs. from Cor. No. 3.

GENERAL DESCRIPTION

This claim is situated in Hayes Canyon at an elevation of about 4,000 ft., and is comprised mainly of bottom land, with a gradual slope to the south.

Approximately 20 acres of the area are suitable for agricultural purposes, of which about 1 acre has been set out to small orchard just north of the house.

There is also evidence of about 5 acres having been under cultivation in the past. The soil is a rich sandy loam of good depth and would produce good crops with irrigation.

Water for domestic use and for watering about 200 head of cattle is obtained from the wells on the claim.

There is no merchantable timber on the claim.

I saw no indication of mineral on the claim.

The claim is mainly valuable for a stock ranch head-quarters for which it is at present being used.

CONFLICTS AND ADJOINING CLAIMS

There are no conflicts or adjoining claims.

Wilcox, Arizona, the nearest postoffice and trading point, situated on the Southern Pacific Railway, is about 20 miles distant in a southerly direction, and is reached by fair wagon road.

Survey completed May 23, 1923.

Surveyor - Forest Service.

Form 85. Sheet No. 3.—Revised Feb., 1915.

Directions.—1. Carry out calculations to two decimals only.

2. In balancing Latitudes and Departures do not obliterate or change the original figures.


Put the corrected figure or figures above in red ink. Do not change the footing of the original figures, but put below them the corrected footing in red ink.

The corrections for balancing fallings should be proportional to the lengths of the lines.

3. In calculations of fallings take result to nearest link. In calculations of N. and S. areas drop all after second decimal. Surveyors are required to use the Standard Field Tables issued by the G. L. O.

4. Only three copies of this tabulation are necessary, for the District Office, the Surveyor General, and the Commissioner.

CORNERS.	BEARING.	DISTANCE.		TUDES.	DEPARTURES.				DOUBLE M. D.		N. AREAS.		G APELG				
			North.		South.		East.		West.		DOUBLE M. D.		N. AREAS.		S. AREAS.		
1 - 2	S. 89°31' E.	30.22				25	30	22			30	23		1	7	26	-
2 = 3	S. 0°46 E.	10.30			10	30	-	14	V - W		60	60			624		/
3 - 4	N. 89°34' W.	30.24		23	/				30	24	30		7	32			
4-1	N. 0°46 W.	10.30	10	30	6					14		14	1	44			
	-	81.06	10	53	10	55	30	36	30	38			8	76	631	44	11
					10	53			30	36					8	76	
Erro	' in Lat. & De	p.				02				02			Man egg		20/622	68	
	Closing	error 1/2	66												31	13	acres V
																	-
		-															
														4			
											1 11 11						



Office of the United States Surveyor General,

Phoenix, Arizona, June 14, 1924 The foregoing field notes of Homestead Entry Survey No.

627

Thomas F. Myers, Surveyor executed by [Forest Service Title] under his special instructions, dated July 21 , 1922, having been critically examined, and the necessary corrections and explanations made, the said field notes, and the surveys they describe, are hereby approved. Tarles M. Donohoe.

I certify that the foregoing transcript of the field notes of the above-described survey in the State of ARIZONA , has been correctly copied from the original notes on file in this office.

CHARLES M, DONOHOE

U. S. Surveyor General.