Form 85 Sheet No. 1 (Revised July 1, 1914.)

U. S. DEPARTMENT OF AGRICULTURE

FOREST SERVICE

FIELD NOTES

RE SINGLES OF THE PARTY.

. HOMESTEAD ENTRY SURVEY NO. 639

SITUATED IN THE COCONINO . NATIONAL FOREST

ADMINISTRATIVE DISTRICT NO. 3

In Section 13 , -surveyed, Township 21 N., Range 8 E. In Section 24 , -surveyed, Township 21 N., Range 8 E.

of the

Gila and Salt River Base & Meridian.

State of Arizona.

Applicant for listing Claude Smith,

Residence Cosnino, Arizona

Application No.

, dated

, 19

List No. 3-4569

, dated May 3

, 1923

Applicant for survey Claude Smith

Residence

H. E. No. 055934

, dated Dec. 11

, 1923.

Land Office

Phoenix, Arizona.

Survey executed by Thomas F. Myers, Surveyor - Forest Service.

Under special instructions dated July 9

, 19 23

Survey commenced

July 23

, 19 23

Survey completed

July 25

, 19 23

Under Acts of June 11, 1906, and February 26, 1923.

OATH OF ASSISTANTS

We hereby certify that we assisted Thomas F. Myers, Surveyor - Forest Service in surveying all those [Forest Service Title.]

parts or portions of Homestead Entry Survey No. 639 , in the State which are represented in the following field notes of Arizona as having been surveyed by him and under his direction; and that said survey has been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the corner monuments established, according to the instructions furnished by the United States Surveyor General for Arizona.

Note: It would have been very expensive and inconvenient to appear before an officer to administer Oaths to Assistantsp hence they were taken by the Surveyor.

Subscribed and sworn to before me this

25th

July

Surveyor - Forest Service.

OATH OF SURVEYOR

Thomas F. Myers, Surveyor - Forest Service, [Forest Service Title.]

1, 19 23.

do solemnly swear that, in strict conformity with the special instructions of the United States Surveyor General for Arizona , dated July 9 , 1923 , and the laws of the United States, I have well, faithfully, and truly, in my own proper person, surveyed a tract of land embraced in

List , No. 3-4569 , dated May 3 Patent , under the Act of , 1923 , for June 11 , 1906 639 the same to be known as Homestead Entry Survey No. National Forest, in Coconino situated within the , Township 21 N. , Range 8 E. , and , Township 21 N. , Range 8 E. , 13 - surveyed Section 24 - surveyed Section

Ari zona of the Gila and Salt River Base & meridian, and the related retracements and resurveys and section subdivisions, which are represented in the following field notes as having been surveyed by me; and I further solemnly swear that all the corners of said survey have been established and perpetuated in strict accordance with the stated special instructions, and in the specific manner described in the field notes, and that the following are the original field notes of such

Thomas & Myers Surveyor - Forest Service.

[Forest Service Title.]

Subscribed and sworn to before me this

9th

January , 1924

Mark Bridge SEAL.

Exhel S. myers Notary Public.

My commission expires: April 12, 1925.

Chains

Applicant for listing, Claude Smith; List No. 3-4569. dated May 3, 1923.

Surveyed under special instructions from the Surveyor General for Arizona, dated July 9, 1923, and designated

Situated in Secs. 13 and 24, T. 21 N., R. 8 E., (surveyed and accepted) Gila and Salt River Base and Meridian, Coconino National Forest, Arizona.

Surveyed under the Acts of June 11, 1906, and February 26, 1923.

Survey commenced July 23, 1923, and executed with a Buff and Buff transit No. 14631, equipped with Smith . solar attachment.

> I test the adjustments of the transit and make necessary corrections.

All distances are horizontal, and were reduced from measurements made directly on the slope with a 400 link steel tape. The slope angles were determined with a clinometer.

. The 'vo . C epied.

July 23, 1923.

At my station near Cor. No. 1 of this survey in Lat. 55,11'50" N., Long. 111°29'30" W. from Forest Service Base Map, at 6h 2lm 12s p.m. 1.m.t., I observe Polaris with telescope direct, reading an angle of 10°47'00" from star to left to reference mark about 1/2 mile distant.

Greenwich m.t. U. C. Polaris, July 24,1923, 5h 30.3m a.m.

Corr. for Long.

1.2

1.m.t. U.C. Polaris, July 24, 1923, 5h 29.1m a.m.

1.m.t. Obsn. Polaris, July 23, 1923, 6h 21.2m p.m.

Hour angle

11h 07.9m

Azimuth of Polaris 0°17.5' E.

Bearing of reference mark N. 10°29.5' W.

HOMESTEAD ENTRY SURVEY NO. 639

COCONINO NATIONAL FOREST

STATE OF ARIZONA

Chains

.2.

At same station at 6h 24m 22s p.m. 1.m.t., I again observe Polaris with telescope reversed, reading an angle of 10°48'30" from star to left to same reference erisons, dated buly 9, 1822, and design desired

> 1.m.t. U.C. Polaris July 24, 1923. 5h 29.1m a.m. 1.m.t. Obsn. Polaris, July 23, 1923, 6h 24.4m p.m. Hour angle 11h 04.7m

Azimuth of Polaris 0°18.6' E. Bearing of reference mark N. 10°29.9° W.

The bearing of the reference mark as determined from the mean of the two observations is N. 10°29.7' W. I accept bearing of reference mark as N. 10°30' W., and from the corresponding meridian all courses of this survey were deflected by sustained angulation.

RETRACEMENT

no July 23, 1923. And . Les modition et account in Ital

Beginning at the 1/4 Cor. between Secs. 13 and 24, T. 21 N., R. 8 E., a limestone 14x10x10 ins. above ground, marked and witnessed as described by the Surveyor General.

Thence S. 89°45' W.

Retracing line between Secs. 13 and 24 W/2. Fall 79 lks. South of/Cor. Secs. 13, and 24, a

limestone 8x10x8 ins. above ground, marked and witnessed as described by the Surveyor General.

True line is N. 89°09' W. 40.93 chs.

July 23, 1923.

BOUNDARIES OF CLAIM

July 24, 1923.

Beginning at Cor. No. 1 and Closing Cor. on line between Secs. 13 and 24.

Deposit a limestone lx2x3 ins., marked with a + 14 ins. in the ground, over which set a limestone 24x6x8 ins.

Chains chiseled + for the point, CC on NE. and 1 HES 639 on NW. face: raise a mound of stone 2 ft. base, 1-1/2 ft. high NE. of Cor: on Closing line, whence:

> A pinon 6 ins. dia. brs. N. 71°25' E. 90 lks. A pinon 8 ins. dia. brs. S. 12°25' E. 114 1ks. Each blazed and scribed CC 1 HES 639 + BT.

1/4 Cor. Between Secs. 13 and 24, previously described, bears S. 89°09' E: 6.30 chs.

Latitude 35°11'45" N., Longitude 111°29'30" W. from Forest Service Base Map.

Mag. decl. at 9 a.m. 15°46' E. Mean Mag. decl. 15°45'

. Ton 'So . A source

Thence S. 45°24' W.

Over bottom land through scattering brush.

1.84

Identical with Cor. H/6 of the list survey, which is a limestone 6x8x8 ins. above ground, marked and witnessed as described by the Forest Service. I destroy all trace of this list Cor.

Deposit a limestone 2x4x4 ins., marked with a + 16 ins. in the ground, over which set a limestone 24x8x10 ins. chiseled + for the point and 2 HES 639 on N. face; raise a mound of stone 2 ft. base 1-1/2 ft. high N. of Cor., whence:

> A pinon 6 ins. dia. brs. S. 9°25' W. 74 lks. A cedar 9 ins. dia. brs. S. 50°26' E. 108 lks. Each blazed and scribed 2 HES 639 + BT.

Thence N. 38°25' W.

Descend 4 ft. over gentle N. slope over open grass land. To Cor. no. 3 and Closing Cor. on line between Secs. . 17508 ... 13 and 24.

Deposit a limestone 1x3x4 ins., marked with a + 15 ins. in the ground, over which set a limestone 24x8x10 ins. chiseled + for the point, CC on SE., 3 HES 639 on NE.

Chains

face; raise a mound of stone 2 ft. base 1-1/2 ft. high SE of Cor., on Closing line, whence:

A pinon 9 ins. dia. brs. S. 57°06' W. 277 lks. A pinon 6 ins. dia. brs. N. 45°05' E. 273 lks. Each blazed and scribed CC 3 HES 639 + BT. 1/4 Cor. between Secs. 13 and 24, previously described, bears S. 89°09' E. 8.67 chs. Cor. Secs. 13, 14, 23 and 24, previously described, bears N. 89°09' W. 32.26 chs. Cor. No. 1, previously described, bears S. 89°09! E. 2.37 chs.

Thence N. 38°25' W.

Over open bottom land.

Arroyo 15 1ks. wide, 2 ft. deep, course NE. Ascend 30 ft. over rolling NE. slope, through dense pinon and cedar. and svede . at 62000 sactionity

Thedes & these

To Cor. No. 4. The property of Section as 25.38

.50

Identical with Cor. H/5 of the list survey, which is a sandstone 20x12x6 ins. above ground, marked and witnessed as described by the Forest Service. I destroy all trace of this list. Cor.

Deposit a limestone 1x3x4 ins., marked with a + 14 ins. in the ground, over which set a limestone 24x10x16 ins. chiseled + for the point and 4 HES 639 on E. face; raise a mound of stone 2 ft. base 1-1/2 ft. high E. of

A pinon 9 ins. dia. brs. S. 14°12' E. 48 lks. A pinon 12 ins. dia. brs. S. 61°30' W. 551ks. Each blazed and scribed 4 HES 639 + BT.

Thence N. 8°37' W.

Descend 50 ft. over NW. slope through scattering pine. pinon and cedar.

Bottom of descent, thence over bottom land.

			A
	STATE OF	ARIZONA	
			- 2

Chains 6.50

Road bears E. and W.

7.55

Arroyo 10 lks. wide, 2 ft. deep, course E.

10.20

Begin ascent of 10 ft. over SE. slope through scattering pine, pinon and cedar.

a of a content

13.00

To Cor. No. 5.

Identical with Cor. H/4 of the list survey, which is a sandstone 5x10x10 ins. above ground, marked and witnessed as described by the Forest Service. I destroy all trace of this list Cor.

Deposit a limestone 2x6x7 ins., marked with a + 10 ins.
in the ground, to solid rock, over which set a limestone 24x6x10 ins., chiseled + for the point and 5 HES
639 on SE. face; raise a mound of stone 2 ft. base,
1-1/2 ft. high, SE. of Cor., whence:

A pine 24 ins. dia. brs. S. 43°56' E. 219 lks. A pine 15 ins. dia. brs. S. 5°48' W. 180 lks. Each blazed and scribed 5 HES 639 + BT.

Thence S. 88°46' E.

Over rolling rocky land through edge of heavy pinon and cedar.

20.13

To Cor. No. 6.

Identical with Cor. H/3 of the list survey, which is a limestone 10x12x12 ins. above ground, marked and witnessed as described by the Forest Service. I destroy all trace of this list Cor.

Deposit a limestone 2x4x6 ins., marked with a + 20 ins. in the ground, over which set a limestone 30x18x10 ins. chiseled + for the point and 6 HES 639 on S. face; raise a mound of stone 2 ft. base, 1-1/2 ft. high S. of Cor., whence:

A pinon 9 ins. dia. brs. N. 11°35' W. 56 lks.

A pinon 12 ins. dia. brs. N. 12°02' E. 121 lks.

Each blazed and scribed 6 HES 639 + BT.

July 24, 1923.

8-224

STATE OF ARIZONA

Chains

July 25, 1923.

Thence N. 50°23' E.

Over rolling rocky land through edge of heavy pinon and cedar.

. and .. ares been 00.5

28.10

To Cor. No. 7. / Part the state , onto

Identical with Cor. H/2 of the list survey, which is a limestone 8x10x8 ins. above ground, marked and witnessed as described by the Forest Service. I destroy all trace of this list Cor.

Deposit a limestone 2x4x4 ins., marked with a + 10 ins. in the ground, to solid rock, over which set a limestone 20x4x12 ins., no longer stone available, chiseled + for the point and 7 HES 639 on S. face; raise a mound of stone 2 ft. base, 1-1/2 ft. high S. of Cor., whence:

A pinon 12 ins. dia. brs. N. 69°44' W. 15 1ks.

A pinon 11 ins. dia. brs. N. 37°54' E. 22 1ks.

Each blazed and scribed 7 HES 639 + BT.

Thence S. 75°14' E.

Over gently rolling open grass land.

20.02

To Cor. No. 8.

Identical with Cor. H/l of the list survey, which is a limestone 7x10x10 ins. above ground, marked and witnessed as described by the Forest Service. I destroy all trace of this list Cor.

Deposit a limestone 2x5x5 ins., marked with a + 16 ins. in the ground, over which set a limestone 24x10x4 ins. chiseled + for the point and 8 HES 639 on SW. face; raise a mound of stone 2 ft. base 1-1/2 ft. high SW. of Cor., whence:

A pine 20 ins. dia. brs. N. 14°02' E. 301 lks.

A pinon 14 ins. dia. brs. N. 67°37' E. 347 lks.

Each blazed and scribed 8 HES 639 + BT.

1/4 Cor. between Secs. 13 and 18, a limestone

.

9

STATE OF ARIZONA Chains 12x8x10 ins. above ground, marked and witnessed as described by the Surveyor General, bears S. 44°41' E. 7.09 chs. by direct measurement. Thence S. 0°48 W. . 300 Ascend gradually 30 ft. over open N. slope. Top of ascent. Thence over level mesa land through 16.00 heavy cedar and pinon. To Cor. No. 9. 14 104 .. 01 20.06 Identical with Cor. H/8 of the list survey, which is a limestone llx7x16 ins. above ground, marked and witnessed as described by the Forest Service. I destroy all trace of this list Cor. Deposit a limestone 2x2x4 ins., marked with a + 20 ins. in the ground, over which set a limestone 30x10x20 ins. chiseled + for the point and 9 HES 639 on NW. face; raise a mound of stone 2 ft. base 1-1/2 ft. high NW. of Cor., whence: A pinon 6 ins. dia. brs. N. 69°30' W. 17 1ks. A pinon 9 ins. dia. brs. S. 55°30' W. 63 1ks. Each blazed and scribed 9 HES 639 + BT. Thence N. 89°01' W. Ascend 4 ft. over E. slope through pinon and cedar. Top of ascent thence over mesa land. 1.80 Descend 15 ft. over rocky W. slope, through pinon and 3.00 cedar. 3 al abresto helaw oppin wet and con-Bottom of descent. Ascend 20 ft. gradually over E. 7.00 slope through pinon and cedar.

> Identical with Cor. H/7 of the list survey, which is a limestone 4x6x10 ins. above ground, marked and witnessed as described by the Forest Service. I destroy all trace of this list Cor.

To Cor. No. 10.

Chains

Deposit a limestone 2x4x6 ins., marked with a + 14 ins. in the ground, over which set a sandstone 24x11x7 ins. chiseled + for the point and 10 HES 639 on N. face; raise a mound of stone 2 ft. base 1-1/2 ft. high N. of Cor., whence:

A pinon 11 ins. dia. brs. S. 89°15' W. 73 lks.

A cedar 6 ins. dia. brs. S. 28°25' E. 47 lks.

Each blazed and scribed 10 HES 639 + BT.

.C .on . To of

Thence S. 45°24' W.

Over rolling land through heavy pinon and cedar.

To Cor. No. 1, the place of beginning.

. AREA IL wind to conit bis

Area in Sec. 24 - - - - - - - - - - - - - - 154.85 acres

Area in Sec. 24 - - - - - - - - - - - - - - - 155.00 acres

IMPROVEMENTS

There were no improvements on the claim at the time of survey.

GENERAL DESCRIPTION

This claim is situated at the function of three shallow draws and is comprised mainly of open grass park land in the draws. The surrounding hills are low and covered with a heavy stant of pinon and cedar as is also the low ridge which extends in a northeasterly direction through the center of the claim. Approximately 70 acres of the area are suitable for agricultural purposes, of which about 5 acres have been plowed. The soil on the agricultural portion is a rich dark loam of good depth and very fertile; the remainder is suitable for pasture land only.

. Tot well wind to sell to the

COCONINO NATIONAL FOREST

STATE OF ARIZONA

9.

Chains

There is a fairly heavy stand of pinon and cedar on the ridge near the center of the claim, suitable for cordwood only.

I saw no indication of mineral on the claim.

CONFLICTS AND ADJOINING CLAIMS

There are no conflicts or adjoining claims.

Cosnino, Arizona, the nearest settlement and postoffice and railway station on the Atchison, Topeka and Santa Fe Railway, lies about 1-1/2 miles distant in a northessterly direction.

Flagstaff, Arizona, the main trading point in this vicinity, lies about 16 miles distant in a westerly direction.

Survey completed July 25, 1923.

Thomas Thyers
Surveyor - Forest Service.

HOMESTEAD ENTRY SURVEY NO.

NATIONAL FOREST

STATE OF

Maddle (Thing and To revide out their again and column to the again and the property of the format their again and another other of the format		Chains
	The first of the state of the object of the object of the state of the state of the state of the object of the state of the object of the state of t	a more, ore careft of and chiral to contain the contains of the chiral contains of the contains ore

Form 85. Sheet No. 3.—Revised Feb., 1915.

Directions.—1. Carry out calculations to two decimals only.

2. In balancing Latitudes and Departures do not obliterate or change the original figures.


Put the corrected figure or figures above in red ink. Do not change the footing of the original figures, but put below them the corrected footing in red ink.

The corrections for balancing fallings should be proportional to the lengths of the lines.

3. In calculations of fallings take result to nearest link. In calculations of N. and S. areas drop all after second decimal. Surveyors are required to use the Standard Field Tables issued by the G. L. O.

4. Only three copies of this tabulation are necessary, for the District Office, the Surveyor General, and the Commissioner.

CORNERS.	BEARING.	DISTANCE.	LATITUDES.					DEPARTURES.				DOUBLE M. D.		N. AREAS.		S. AREAS.		
			North.		Sou	South.		East.		West.				N. AILEAS.		b. AREAS.		
					The state of	AF	EA IN	SEC.	24				Training.					
1 - 2	S. 45°24' W.	1.84			1	29	13/11		1	31	3	43	ar La Mille			42	-	
2 - 3	N. 38°25' W.	1.70	1	33	7					06		06	1	41				
3 - 1	S. 89°09' E.	2.37				04	2	37	/			37				09	/	
		5.91	1	33	i	33	2	37	2	37	1 1		1	41		51	7	
D	. T															41		
	in Lat. & Dept.:				Wer as the Co										20/_3		-	
	Closing error:	None									-					15	acres	-
3 - 4	N. 38°25' W.	25.38	19	88	7	AH	EA IN	SEC.	13	rt rt	19	~ 77						
4 = 5	N. 8°37' W.				V.		-				-		391					
5 - 6	S. 88°46' E.	13.00	12.			43	•	37	1	95		95	25	06		-		-
6 - 7	N. 50°23° E.	28.10	17	9/	/	45		13	,		20		1108	63	8	66		
7 - 8	S. 75°14' E.	20.02	100		5	10		36	,		102		1100	00	524	70		
8 - 9	S. 0°48' W.	20.06				06	7	-50		28	121		*		2448			
9 - 10	N. 89°01' W.	15.06		26	7				15	06	106		27	73	/			
10 - 1	S. 45°24' W.	36.08			25	33	1000			69	/ 65	1			1669	40	7	
1 - 3	N. 89°09' W.	2.37		04	/				2	37	37	81	1	51	J			
		180.20	AND DESCRIPTION OF THE PARTY OF	96	50	92	61	14	61	12			1553	97	46.50	99	/	
			50	2			61	12							1553	97	7	
Error	in Lat. & Dep.)4				02							20/3097	-	V	
	Closing error	1/4029													154.	85 a	cres 4	-



APPROVAL

Office of the United States Surveyor General,

Phoenix, Arizona, April 4 , 1924

The foregoing field notes of Homestead Entry Survey No.

639

executed by Thomas F. Myers, Surveyor [Forest Service Title] under his special instructions, dated July 9 , 1923, having been critically examined, and the necessary corrections and explanations made, the said field notes, and the surveys they describe, are hereby approved. Garles M. Donohoe.

U. S. Surveyor General.

I certify that the foregoing transcript of the field notes of the above-described survey in the State of Arizona correctly copied from the original notes on file in this office.

Charles M. Donohoe

8-2349

U. S. Surveyor General.