Form 85 Sheet No. 1 (Revised July 1, 1914.)

# U. S. DEPARTMENT OF AGRICULTURE

FOREST SERVICE

## FIELD NOTES

EXCHANGE

SITUATED IN THE SITGREAVES NATIONAL FOREST

ADMINISTRATIVE DISTRICT NO.3

In Section 23 , surveyed, Township 9 N., Range 22 E.

Resurvey line between Secs. 23 and 24

Retracement line between Secs. 13 & 14

" W/2 line " Secs. 13 & 24

Retracement E/2 line between Secs. 23 & 26

of the T. 9 N., R. 22 E.

Gila and Salt River Base and Meridian.

State of

Arizona.

XXXXXXXXXXXXXXXXXXXX

XXXXXXXXX

SCHOOL STATEMENT

HEEK KOKKERK

Survey executed by Thomas F. Myers, Chief Surveyor, Forest Service

Under special instructions dated August 20 , 19 26

Survey commenced

March 1

, 19 27 00

Survey completed

March 3

, 19 27

Under Acts of March 20, 1922, and May 11, 1926.

OVER

We hereby certify that we assisted

Thomas F. Myers

Chief Sprveyor, Forest Service [Forest Service Title.]

in surveying all those

, in the State parts or portions of Homestead Entry Survey No. 649 which are represented in the following field notes of Arizona as having been surveyed by him and under his direction; and that said survey has been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the corner monuments established, according to the instructions furnished by the United States Surveyor General for Arizona.

Note: It would have been very expensive and incon-venient to appear before an officer to administer Oaths to Assistants; hence they were taken by the Surveyor.

Subscribed and sworn to before me this

Ohief Luxueyor

OATH OF SURVEYOR

Thomas F. Myers, Chief Surveyor, Forest Service [Forest Service Title.]

do solemnly swear that, in strict conformity with the special instructions of the United States Surveyor General for Arizona, dated August 20, 19 26, and the laws of the United States, I have well, faithfully, and truly, in my own proper person, surveyed a tract of land

> for Exchange

of the Gila and Salt River Base & meridian, Arizona , and the related retracements and resurveys and section subdivisions, which are represented in the following field notes as having been surveyed by me; and I further solemnly swear that all the corners of said survey have been established and perpetuated in strict accordance with the stated special instructions, and in the specific manner described in the field notes, and that the following are the original field notes of such

Thomas & Muyers
Chief Luveyor
[Verest Service Title.]

Subscribed and sworn to before me this

march

, 1927.

Bonnie M. Brewer notary Oublic

SEAL.

1 ....

My Commission Expires Sept. 30, 1928

# HOMESTEAD ENTRY SURVEY NO. 649

## SITGREAVES NATIONAL FOREST

STATE OF ARIZONA.

1.

Chains

The tract of land embraced in this survey is in private ownership and was surveyed for acquisition by the United States under the Acts of March 20, 1922, and May 11, 1926.

Surveyed under special instructions of the Office of Public Surveys, for the State of Arizona, dated August 20, 1926; surveyed under the Acts of March 20, 1922, and May 11, 1926.

Survey commenced March 1, 1927, and executed with a Berger Light

Mountain Transit No. 12484.

I test the adjustments of the transit and make necessary corrections.

All distances are horizontal and were reduced from measurements made directly on the slopes with a 400 link steel tape. The slope angles were determined with a clinometer.

ens made by C. P. long, Matrict Engineer, Forest Service,

March 1, 1927, a standid open elaway of , SSSI , ad a more

At my station near Cor. No. 1 of HES. 206, hereinafter described in Latitude 34°10°33" N., Longitude 109°58°30" W. from Forest Service Base Map, at 5 h. 10 m. 32 s. p.m. 1.m.t., I observe Polaris with telescope direct, reading an angle of 90°10°00" from star to right to reference mark; about 20 chs. distant.

Greenwich M.T. U.C. Polaris, March 1, 1927, 3 h. 0.7m. OOs. p.m.

l.m.t. U.C. Polaris, March 1, 1927, 2 h.59.5m. 00s. p.m.

Hour angle bes slim ero diron asuit . oed o2 h. 11.0m. 00s.

1.met. Observation Polaris, March 1, 1927, 5 helo.5me OOse peme

Azimuth of Polaris of aid . 300 .0043.10 We are and do w

Bearing of reference mark N.89°26'.9 E.,

Polaris with telescope reversed reading an angle of 90°10° from

lomet. U.C. Polaris March 1, 1927, 2 h. 59.5 m. p.m.

Hour angle Hour angle 100 and we bedingen as beared in 2 h. 13.3 m.

Thomas 5. 0046 W.

## SITGREAVES NATIONAL FOREST

STATE OF ARIZONA.

2.

Chains

drivita

2200

Thence S. 0046 We

Azimuth of Polaris

Bearing of Reference Mark N.89°26'.2 E.

The bearing of reference mark as determined from the mean of the two observations is N. 89°26°.6 E. I accept bearing of reference mark as N. 89°27' E., and from the corresponding meridian all courses of this survey were deflected by sustained angulation. Note: My watch is set for 105th meridian time and compared with Western Union at Albuquerque on February 28, 1927, and found to be correcte to bia change out to strantaufbe out fort I

## BREAR MOTING THOS BY BY RETRACEMENT. BY BENETITED ILL

March 1, 1927. atl the and a secole and no ylderic sham

A determination of the position for Cor. Secs. 13, 14, 23 and 24 was made by C. A. Long, District Engineer, Forest Service, on Augus t 24, 1926, by double proportionate measurements from the Section Corners 1 mile north and south and from the 1/4 Sec. Corners 1/2 mile East and West. The position thus determined results in an elimination of the road exception along the West boundary of HES. 206 (surveyed by C.A. Long, September 2 to 7, 1914). The position of the Cor. Secs. 13,14,23 and 24 determined by me by running S 89°27° W. 50 1ks. from Cor. No. 1 of HES. 206, thence S. 0°46' W.19.72 chs. places this core on the east side of a cattle guard and Cor. of fence from which the fences bear South and East. By using the position for the Core thus determined the retracement of the Sec. lines North one mile and East 1/2 mile agrees with the record of HES. 206. This position is further verified by the fact that the point falls in the edge of an old mound of small stone similar to those of the other original corners which are in places or gallers occurred equivales of the strelet I therefore reestablish the corner of Sections 13, 14, 23 and 24 from the record of H.E.S. 206 as follows:

Beginning at the Cor. of Secs. 11, 12, 13 and 14, a malpais stone,

marked and witnessed as described by the Office of Public Surveys.

### EXCHANGE HOMESTEAD-ENTRY SURVEY NO. 649

SITGREAVES NATIONAL FOREST

.4 3.

STATE OF ARIZONA

•	STATE OF CLARIZONA.
Chains	Retracing line between secs. 13 and 14.
20.22	Fall 50 lks. west of Cor. No. 2 of H.E.S. 206, a malpais stone
	9x7x10 ins. above ground, marked and witnessed as described by
. be	the Office of Public Surveys.
39.44	1/4 Sec. Cor. has been destroyed. Point for Cor. falls in center
	of road. Just - 33 par al . sould consider soul nobies &
59.18	Fall 50 1ks. S. 89°27' W. of Cor. No. 1 of H.E.S. 206, a basalt
en enit	stone 6x6x10 ins. above ground, marked and witnessed as described
	by Office of Public Surveys.
	Cor. No. 9 of H.E.S. 206, a malpais stone 8x4x10 ins. above ground,
	marked and witnessed as described by Office of Public Surveys,
	flag on which is plainly visible, bears N. 89°27° E. 19.96 lks.
	distant.
78.90	Set temporary point for Cor. Secs. 13, 14, 23 and 24. Point is
dae	on east side of road and falls in small mound of stone, which
07	15 July Horal of Colo of Lands Lands
	** average office to . J. 10 edd we protect to Leave . In
	From the temporary point for Cor. Secs. 13, 14, 23 and 24.
	Thence S. 89°50' E. S. A. C. S
at 1 be	Retracing line between Secs. 13 and 24 along outside of fence.
40.32	Intersect the 1/4 cor. between Secs. 13 and 24, which is a basalt
	* stone, set in small mound of stone, marked and witnessed as des-
they	cribed by Office of Public Surveys.
24. 50	11.00
	The methods woods
	At the point for Cor. Secs. 13,14,23 and 24, as above determined,
1987	
	on brass cap.
Section 1	to a mass of the second
	1926 on South rim
	U 10 III II
No. 58	40.08 Jan Mar Mar Mar Sec. Cor. bet den Swire 28 France

S 23 in SW and see of the beat the plant deed sont

S 24 in SE quadrants, from which I take new bearing tree as follows:

4.

## EXCHANGE HOMESONBAD SHREET SURVEY NO .- 649

SITGREAVES NATIONAL FOREST

STATE OF ARIZONA.

Chains	A yellow pine 16ins. dia. blazed and scribed T 9 N R 22 E S 23
9.700	bears 8 8°56 W. 135 lks
and but	Win ruph is because have been experted and Olyland
	From the Cor. Secs. 13, 14, 23 and 24, previously described .
redner	Thence West 102 dailor destroyed and and to dest all alace
	On random line between Secs. 14 and 23 - East half.
39.47	Fall 25 lks. north of 1/4 Sec. Cor. between Secs. 14 and 23, a
hedini	basalt stone, marked and witnessed as described by the Office
	of Public Surveys.
*percent	True line is S. 89°38' W. 39.47'
.24	rolls of the to be mall will bed to such as horseart by one best or
e ilre,	Return to Cor. Secs. 13,14,23 and 24, previously described.
	Thence South.
al dai	Retracing line between Secs. 23 and 24.
80.38	Fall 56 1ks. West of Cor. Secs. 23,24,25 and 26, an iron post
	2 ins. dia. 12 ins. above ground, with brass cap, marked and
	witnessed as described by the Office of Public Surveys.
	Thence N. 0°24° W
	On true line between Secs. 23 and 24. 100 68 .2 corent
20.095	Set a malpais stone 20x10x10 ins., 12 ins. in ground, marked 1/16
di saed .	on W. face for 1/16 Sec. Cor. on East boundary SE/4 Sec. 23;
s den-	raise mound of stone West of Cor. No witnesses available.
40.19	Set a malpais stone 20x8x12 ins. in ground, marked 1/4 on West
broom	face for reestablished 1/4 Sec. Cor. between Secs. 23 and 24. No
	witnesses available. Point is in edge of cultivated field.
80.38	The Cor. Secs. 13, 14, 23 and 24, previously described.
Doc vere	March 1, 1927.
	March 2, 1927.
	From the Cor. to Secs. 23, 24, 25 and 26, previously described.
	Thence West.
	On random line between Secs. 23 and 26 (Record S. 89°45° W.)
40.02	Fall 38 1/2 lks. N. of 1/4 Sec. Cor. between Secs. 23 and 26, an
	iron post firmly set, marked and witnessed as described by the

s 24 in St quidrants, from which I take new bearing tree as follows:

.0

## STATE OF ARIZONA

Chains	Office of Public Surveys.
	Thence N. 89°27° E.
er a	on true line between Secs. 23 and 26.
20.01	Set a malpais stone 20x18x6 ins. 12 ins. in ground, marked + on top
27.08	and 1/15 on N. face for 1/16 Sec. Cor. on South boundary of SE/4
	Sec. 23. Raise mound of stone 3 ft. base, 2 ft. high north of Cor.
40.02	Intersect the Cor. Secs. 23, 24, 25 and 26, previously described.
What	From the 1/4 Sec. Cor. between Secs. 14 and 23, previously described.
neather	
1100.	On random meridional line through center Sec. 23.
80.68	Intersect the 1/4 Sec. Cor. between Secs. 23 and 26 previously
	described. Ted sec. Sec. Sec. Sec. Sec. Sec. Sec. Sec. S
. bed	Thence North ag 23 bas 35 .seed assuted .set all ed 58.07
	On true Meridional 1/4 Sec. line through center Sec. 23.
20.17	Set temporary point for 1/16 Sec. Cor. center 8/2.
40.34	Set temporary point center 1/4 Sec. Cor. *hedironeh vi
80.68	Intersect 1/4 Sec. Cor. between Secs. 14 and 23 previously describ-
	ed. 82 rendon lebitudinel 1/16 Sec. bine through center SB.66
	Return to 1/4 Sec. Cor. between Secs. 23 and 24 previously described.
	Thence West.
	On random latitudinal line through center Sec. 23.
79.63	Fall 35 lks. North of point for 1/4 Sec. Cor. between Secs. 22
	and 23, which I restore from witness trees. The original corner
	has been destroyed. Set a malpais stone 25x6x18 ins. 18 ins. in
-aucive	ground, marked 1/4 on West face, whence:
	An oak 10 ins. dia. now badly decayed, marked 1/4 S B T bears Ne
	66°00° W. 65 lks. (original BT.)
	A yellow pine 20 ins. dia. marked 1/4 S BT bears S. 85° E. 13 1ks.
190*	(original BT) 1000 . H coil . oel 81   Inclinative converted 81.05
,64	The notes describe this bearing tree as being an oak. I cut into
-amolve	the pine tree and find original marks. I count the growth rings,
	which number 43, which would fix the time it was blazed and scribed
Restaurant Control	

5.

45

ı	Z	r		
ı	ξ	)	6	۸
			ì	1

	STITE OF MILIOURS
Chains	as 1883.
	I establish new bearing trees.
	A yellow pine 24 ins. dia. blazed andscribed 1/4 S 23 BT bears
und no. 4	S. 63°E. 41 1ks.  but he become it and of and example and a declar a sec (0.0)
35/4	A yellow pine 20 ins. dia. blazed and scribed 1/4 S 22 BT bears
*200 fo	S. 64°45° W. 147 1ks.
*book	Thence N. 89°45° E. Sec. 23, 24, 25 and 35 secretary constructly c
	On true latitudinal 1/4 Sec. line through Sec. 23.
39.89	Intersect meridional 1/4 Sec. line north 20 lks. from temporary
	point for center 1/4 Sec. Cor. I move temporary points for center
	1/4 Sec. Cor. and 1/16 Sec. Cor. center S/2 North 20 and 10 1ks.
W	respectively. 23 . seed neonaed . ned . ned 2 2/1 ets deservoor 80.08
59.76	Set temporary point for 1/16 Sec. Cor. center E/2
79.63	The 1/4 Sec. Cor. between Secs. 23 and 24 previously described.
	The section of particular to the forest control of
	Return to 1/16 Sec. Cor. on East boundary Sec. 23 - SE/4 previous-
	ly described
-diread	Micora Wood
	On random latitudinal 1/16 Sec. line through center SE/4.
39.88	Fall 21 1ks. North of temporary 1/16 Sec. Cor. center S/2.
hor insect	Thence N. 89°42 . E.
	On true latitudinal 1/16 Sec. line through center SE/4.
19.94	Set temporary 1/16 Sec. Cor. center SE/4.
39.88	The 1/16 Sec. Cor. on East boundary Sec. 23 SE/4 previously de-
785 (309	scribed
EL of	mi al .est birkros enois simples a deb . Degressen rend ami
	Return to 1/16 Sec. Cor. on South boundary Sec. 23, SE/4 previous-
oil e	ly described.
	Thence North. (.18 faction) . rsf 68 . 1 100 36
**************************************	'On random meridional 1/16 Sec. line through center SE/4.
1 32,000	Intersect latitudinal 1/16 Sec. line N. 800421 m 2 3

20.18

40.30

Intersect latitudinal 1/16 Sec. line N. 89042: E. 7 lks. from temporary point for 1/16 Cor. center SE/4 previously recorded. Fall 15 lks. East of temporary 1/16 Sec. Cor. center E/2 previously recorded.

#### EXCHANGE HOMESTEAD ENTRY SURVEY NO: 649

SITGREAVES NATIONAL FOREST

#### STATE OF ARIZONA.

Chains

True line is S. 0°13! E. 40.30 chs.

An oak lS ins. dis. I move temporary point for 1/16 Sec. Cor. center SE/4, S. 89°42° W. 1/2 lk. 89°42' E.

Whence temporary 1/16 center S/2 bears S. 89°42' W. 19.935 chs. 1/16 Cor. on E. boundary SE/4 bears N. 89°42° E. 19.945 chs.

March 2, 1927.

Theres S. 890421 W.

20 Cor. To. 4.

8.79

#### BOUNDARIES OF EXCHANGE SURVEY NO.649

March 3, 1927.

. Beginning at Cor. No. 1, also 1/16 Sec. Cor. center E/2 Sec. 23. Deposit a malpais stone 2x3x4 ins. marked with a + 16 ins. in. ground, over which set a malpais stone 24x8x12 ins., marked + on top and 1 ES 649 on SW face and 1/16 on E. face; raise mound of stone 3 ft. base, 2 ft. high SW. of Cor., whence:

A pine 8 ins. dia. blazed and scribed 1/16 I ES 649 + BT bears tosad .478. 130481 E. 04601ks. Let tenst EN no 848 ER & bue gos no

A pine 24 ins. dia. blazed and scribed 1/16 I ES 649 + BT bears Nec29058 W: 5601ks os beseld , . slo .ant 81 480 m

The 1/4 Sec. Cor. between Secs. 23 and 24 previously described . Bears N. 89045 E. 19.87 chs. distant.

> Latitude 34°09'41" N. Longitude 109°58'50" W. from Forest Service Base Map.

The Magnetic declination at 8 a.m. is 14030 E., mean Mag. decl. \*14027 to Eat blo , well hearthing gamer stable to sibe good

Thence S. 0º13'F.

On meridional 1/16 Sec. line through center SE/4 Sec. 23.

Center lane bears East and South. 19.92

To Cor. No. 2 and 1/16 Sec. Cor. at center SE/4 Sec. 23. 20.12

Deposit a malpais stone 3x3x4 ins., marked with a + 16 ins. in ground, over which set a malpais stone 24x10x12 ins., marked +

on top, 2 ES 649 on NW. face and 1/16 on E. face, whence;

A pine 26 ins. dia. blazed and scribed 2 + ES 649 BT bears S.510 F. BEREST W. 88 lime. distant. 20' W. 101 1ks.

steed TE

grand TE

## EXCHANGE HOMESTEAD ENTRY SURVEY NO. 649

SITGREAVES NATIONAL FOREST

8		STATE OF ARIZONA.
		An oak 16 ins. dia., blazed and scribed 2 + ES 649 BT bears N.  56°50° W. 155 lks.  The 1/16 Sec. Cor. on E. Boundary SE/4 Sec. 23 bears N. 89°42° E.  19.945 chs. and  1/16 Sec. Cor. on S. boundary SE/4 Sec. 23 bears S. 0°13° E.  20.18 chs.
		BOUDDERES OF REDAMER SURV N. 10. 249
		Thence S. 89°42° W
	. 83 . D	Along latitudinal 1/16 Sec. line through center SE/4 Sec. 23.
No. of London	•21	Road, bears North and Southers and a keelen a draged
	.54	Road to Lakeside Station bears N. and S
	3.30	esTo-Core Noe 3. State son vo no es no I bus que no
		Deposit a malpais stone 3x4x4 ins., marked with a + 16 ins. in
	\$.76m	ground, over which set a malpais stone 24x10x14 inse, marked +
		on top and 3 ES 649 on NE face; raise mound of stone 2 ft. base,
	annoc	1,1/2 ft. high NE. of Cor., whence:
		An oak 16 ins. dia. , blazed and scribed 3 + ES 649 bears N. 66°
	badi	pul4' E. 74 lks. AS bas &S . soed reserted . Tol . tol all ent
		A pine 12 ins. dia. blazed and scribed 3 + ES 649 bears S. 15° E.
	ectvrol	62 olks "03'880'801 obbut not . " "12'00'48 obisided
		Brade Paper
	.Insb	Thence N. 36°52 Wet .m. & to moliarife ab riverse ear
		Along edge of dense young pine and along old fence line.
Market and	8.79	To Core No. 4.
		Deposit a malpais stone 2x4x4 ins., marked with a + 16 ins. in
STATE OF THE		the ground, over which set a malpais stone 24x4x14 ins., marked
		a + on top and 4 ES 649 on E. face.
STATE OF STA	at .	Raise mound of stone 3 ft. base, 2 ft. high E. of Cor., whence:
	+ 500	A yellow pine 14 ins. dia., blazed and scribed 4 + ES 649 BT bears

N. 69°47° E. 85 lks. distant. A yellow pine 12 ins. dia., blazed and scribed 4 + ES 649 BT bears N. 66°28' W. 33 lks. distant. . 201 JOI . N 103

#### EXCHANGE HOMESTFAD\_ENTRY\_SURVEY\_NO. 649

SITGREAVES NATIONAL FOREST

STATE OF ARIZONA.

#9

Chains Thence N. 3º 40' E. Descend gradual N. slope through pine reproduction and along old fence line. 3.76 To Cor. No. 5. 5. 54°251 E. 70 Mes. discont. Deposit a malpais stone 4x4x8 ins., marked with a + 16 ins. in the ground, over which set a malpais stone 24x8x12 ins., marked a + on top and 5 ES 649 on SE face. Raise mound of stone 3 ft. base, 2 ft. high SE. of Cor., whence: An oak 12 ins. dia. blazed and scribed 5 + ES 649 BT. bears N. 54°47° E. 91 1ks. distant. A yellow pine 26 ins. dia. blazed and scribed 5 + ES 649 BT. bears S. 41°00° E. 61 lks. distant. a select place to accept the possible and of enter wolfer a Along gradual N. slope, through scattering pine timber, and along . Substation and ve . Wilsons old fence line. Core of fence from which fences bear west and N. 49047 E. Con-1.00 tinue along E. side of fence 3 lks. distant. 2.78 To Cor. No. 6, a malpais stone in place, showing 14x20x6 ins. above ground. I chisel a + for the point and 6 ES 649 on SE face. Raise mound of stone 3 ft. base, 2 ft. high SE. of Cor., whence: An oak 14 ins. dia., blazed and scribed 6 + ES 649 BT bears S.12° 15° W. 14 lks. distant. A yellow pine 6 ins. dia., blazed and scribed 6 + ES 649 BT bears S. 70°15° E. 15 lks. distant.

Thence N. 17º36 E.

Through dense pine reproduction and along E. side of wire fence 3 lks. distant.

Will , & doubt bede lauce years

3.18 To Cor. No. 7.

> Deposit a malpais stone 4x4x5 ins., marked with a + 18 ins. in the ground, over which set a malpais stone 28x6x12 ins., marked

## EXCHANGE HOMESTEAD ENTRY SURVEY NO. 649

SITGREAVES NATIONAL FOREST

#10

### STATE OF ARIZONA

Chains	The Manual Change W. at Apr S.
olo so	a + on ton and 7 Es 649 on E. face. Raise mound of stone 3 fte
	base, 2 ft. high East of Cor., whence:
	A yellow pine 18 ins. dia., blazed and scribed 7 + ES 649 BT bears
ni.	S. 54°25° E. 70 lks. distant.
bestrad	Thence No. 30521 E. siseiss a tea folds sevo . On ong ent
0.32	Along E. side of wire fence 4 lks. distant.
4.50	To Cor. No. 8 on latitudinal 1/4 Sec. line through center of Sec.
i i e	23. Deposit a malpais stone 3x4x4 ins., marked with a + 18 ins.
	in the ground, over which set a malpais stone 28x10x14 ins.,
stred .T	marked a + on top and 8 ES 649 on SE face. Raise mound of stone
	3 ft. base, 2 ft. high SE. of Cor., whence:
	A yellow pine 26 ins. dia., blazed and scribed 8 + ES 649 BT.
	bears S. 79°15° E. 60 lks. distant.
gnole b	An cak 12 ins. dia., blazed and scribed 8 + ES 649 BT bears S.
	2°08° E. 97 lks. distante .emif const afo
-non	The temporary point for center 1/4 Sec. Cor. of Sec. 23, previ-
	ously recorded bears S. 89°45° W. 15.02 chs. distant.
*81	Thence N. 89°45° E.
se face.	Along latitudinal 1/4 Sec. line through Sec. 23.
	Fence, bears WNW and ESE.
1.00	Road bears N. and S.
1.70	Cor. fence, fences bear N. and West.
3.50	Billie Creek, 10 lks. wide, 6 ins. deep, course NW.
4.85	To Cor. No. 1, the place of beginning.
enna i rejo artistatati i arii 100 ne s	ADVIA
	AREA towns encons
eome?	Total Area 12.58 Acres
	Survey completed March 3, 1927.
ei .	Thomas & Mere

Serveyor, ont Sixox8S ences a regian a sea do how to to Danger

Form \$5. Sheet No. 3.—Revised Feb., 1915.

Directions.—1. Carry out cal planting beatudes and Departures do not obliterate or change the original figures.

2. In balancing beatudes and Departures do not obliterate or change the original figures.

Put the corrected figure or figures above in red ink. Do not change the footing of the original figures, but put below them the corrected footing in red ink.


The corrections for balancing fallings should be proportional to the lengths of the lines.

3. In calculations of fallings take result to nearest link. In calculations of N. and S. areas drop all after second decimal. Surveyors are required to use the Standard Field Tables issued by the G. L. O.

4. Only three copies of this tabulation are necessary, for the District Office, the Surveyor General, and the Commissioner.

TARITMO AND CATOURATIONS OF HOMESBEAD EMBRY SUPPLY NO. 649

CORNERS.	BEARING.	DISTANCE.	LATITUDES.				DEPARTURES.				DOUBLE M. D.		N. AREAS.	S. AREAS.	
			Nort	H.	Sou	гн.	EAS	sT.	West			22. 2.	ii. Illumo.	S. AIUSA	5.
1 - 2	S 0°13° E.	20.12			20	12		08			17	04		342	50
2 - 3	S.89°42' W.	3.30				02 ′			3	30 ′	The state of the s	84			28
3 - 4	N.36°52° ₩.	8.79	7	03	1 to 2 th					27		27	37 05		-60
4 - 5	N. 3°40° E.	3.76	3	75				24				24	90		District Research
5 - 6	N. 49°47°E.	2.78	1	80 ′			2	12'			2.	60	4 68		
6 - 7	N.17°36' E.	3.18	3	03 /				96			5	68	17 21/		
7 - 8	N. 3°52° E.	4.50	4	49/				30 /			6	94	31 16 '		
8 - 1	N.89°45° E.	4.85		02/			4	85				09	24		
		51,28	20	12	20	14	8	7	8	57	fuga leta dues		91 24	342	78
		The second			20	12	1-1-2-1		. 8			105			24
Er	ror in Lat. and De	ep.				02'		r design		02/				20/ 251	54
	Closing error	1/1813								VIV				12	58 acres
		The beautiful to	Closur	e E/2	Sec. 2	3.									
	North	80.68	80				James 5					aligur.			
	N. 89°38° E.	39.47		25			39	47							Sing Military
	S. 0°24° E.	80.38			80	38		56			121 per 1				Edition Edition
	S. 89°27° W.	40.02		#A.		38 /			40	02					
			80	93	80	76	40	03	40 (	-					
			80	76			40	02	Sada Sa		F				
				17/				01							
											tu, to				
			1				<b>V</b>		Let Circi		Mes III W				



### APPROVAL

PUBLIC SURVEY OFFICE, Office-of the United States Surveyor-General,

Phoenix, Arizona, March 28, 1927

Exchange
The foregoing field notes of Homestead Entry Survey No.

649

executed by Thomas F. Myers, Chief Surveyor,
under his special instructions, dated August 20 , 1926, having
been critically examined, and the necessary corrections and explanations
made, the said field notes, and the surveys they describe, are hereby
approved.

-- U-S-Surreyor-General. Office Cadastral Engineer.

I certify that the foregoing transcript of the field notes of the above-described survey in the State of Arizona . has been correctly copied from the original notes on file in this office.

John D. Adams

-U.- S: -Surveyor General.

Office Cadastral Engineer

16 New of Committee of the Committee of the