U. S. DEPARTMENT OF AGRICULTURE Shown on Jp.

Index card

FOREST SERVICE

FIELD NOTES

OF

EXCHANGE XHOMESURANX SURVEY NO. 676

12 3 13 20 10

SITUATED IN THE COCONINO NATIONAL FOREST

ADMINISTRATIVE DISTRICT NO.

In Section 14

Township 21 N. , Range 9 E.

of the

Gila & Salt River Base Me Meridian

State of Arizona

State of

Applicant for kixxing exchange - AT&SF Railroad Company

Residence

Application No. , dated

, 19

List No.

, dated

, 19

Applicant for survey

Residence

H. E. No.

, dated

, 19

Land Office

Survey executed by Aaron F. Jones

Civil Engineer
(Forest Service Title.)

Under special instructions dated

April 23

, 1947

Survey commenced

June 4

, 1947

Survey completed

June 17 , 1947

Under Acts of 3/20/22 and 7/12/43

[OVER]

We hereby certify that we assisted Aaron F. Jones

Civil Engineer

in surveying all those

parts or portions of **Exchange** parts or portions of **Exchange** parts or portions of **Which are represented in the following field notes as having been surveyed by him and under his direction; and that said survey has been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the corner monuments established, according to the instructions furnished by the United States Surveyor General for

Arrille & Beisley Oscar & Holling

Subscribed and sworn to before me this

22nd

day of

July

, 1947

My commission expires Dec. 16, 1949.

Joseph Lucero Lucero

Notary Public

OATH OF SURVEYOR

I, Aaron F. Jones

Civil Engineer
[Forest Service Title.]

do solemnly swear that, in strict conformity with the special instructions of the Write Kurrey Office for Arizona, dated April 23, 19 47, and the laws of the United States, I have well, faithfully, and truly, in my own proper person, surveyed a tract of land

of the **Gila & Salt River Base &** meridian, , and the related retracements and resurveys and section subdivisions, which are represented in the following field notes as having been surveyed by me; and I further solemnly swear that all the corners of said survey have been established and perpetuated in strict accordance with the stated special instructions, and in the specific manner described in the field notes, and that the following are the original field notes of such survey.

Civil Engineer

Subscribed and sworn to before me this

[Forest Service Title.]

4 th

day of

8-2349

notary Public

MY COMMISSION EXPIRES JANUARY 14, 1950

EXCHANGE HOMESTEADXENTRY SURVEY NO. 676

COCONINO NATIONAL FOREST

STATE OF ARIZONA TO STATE

Chains

*8 *55

OM'IJ

solthono-

agt t

."0 4 BALL

eround. fero 1930

Caubern a

...toll

bauera .FI Lyon

Survey executed with Buff and Buff Transit No. 14631. The adjustments of the transit were tested and necessary corrections made before beginning the survey.

The measurements were made with a 3-chain steel tape, graduated every link, and tested by comparison with a standard and found to be correct. The measurements were made on the slope, the vertical angles being determined by a clinometer in good adjustment; the field notes show the horizontal equivalents.

As determined from U.S.F.S. base map, the geographic position of the corner of Secs. 14, 15, 22 and 23, T. 21 N., R. 9 E. is as follows: latitude 35° 11' 40" N., and longitude 111° 25' 06" W.

June 9, 1947; near above corner I make aseries of three altitude observations on the sun for azimuth, as follows:

Telescope	Sun	M. S. T. Watch Time	Vertical	Horizontal Angle Flag to Sun
1st observ	etion:	elow the surre	. aut Sreat d	lw innorm
Divect	9+	1.5 77- 04-0°	70° 71 1 00#	0° 26' Right
Reversed	15 to all	4h 13m 00s	39° 47' 00"	359° 58' 30"
				0° 12' 15"
2nd observ	ration:	ment of processing and the following state of the company of the c	State of the state	
Direct	1º4 000	4h 16m Ols .	38° 371 30"	1° 04' 00"
Reversed	. to	4h 17m 39s	39° 49' 00"	0° 36' 00"
cep se fes	Mean	Lih 16m 50s	38° 43' 15"	0° -50° 00"
3rd observ	ation:			
Direct		4h 19m 43s	37° 531 00"	1° 34' 00"
Reversed			38° 07' 00"	1° 06' 00"
voce •sai	Mean	4h 20 26"	38° 00' 00"	1° 20' 00"

By first observation flag bears N. 88° 13' 34" W. By second observation flag bears N. 88° 12' 40" W. By third observation flag bears N. 88° 13' 53" W.

Mean true bearing of flag N. 88° 13' 22" W.

June 12, 1947, near the center of Sec. 14, I make an hour angle observation of Polaris west of the meridian, two readings each with telescope in direct and reversed positions, and measure the horizontal angle from a flag about 40 chains dist. in the direction right to Polaris. south side of Tenoe, escen

Mean watch time of observation 8h 06m 42s (PM) M.S.T. Mean horizontal angle 269° 39' 00" (Right)
Reduced azimuth of Polaris 0° 13' 20" W. Reduced bearing of flag ... S. 89° 52' 20" E.

Watch was checked with Western Union at Flagstaff prior to the observations. Watch fast of local mean time by computed difference in longitude. Oh 25m 40.4s.

> From the meridians thus established the azimuth is carried forward by deflection angles, throughout the survey.

The indicated discrepancy between the two sets of observations is 0° 0'.

The observed magnetic declination is 14° 45° E.

dien. bears U.

8-2349

COCONINO NATIONAL FOREST

STATE OF ARIZONA

2.

Chains

Resurvey of Section Lines T. 21 N., R. 9 E.

Reestablishment of the survey executed by Caudle and Caudle in 1902

Preliminary to the resurvey, the lines of the original survey were retraced and diligent search was made for all old corners. The retracement data were thoroughly verified and only the true line field notes are given herein.

The point for corner of Secs. 14, 15, 22 and 23 falls in south edge of a road which runs through a cultivated field. No evidence could be found of the original corner monument, nor could its original position be determined by any collateral evidence or testimony of old residents.

At point for corner determined by the method of double proportion

Set an iron pipe, 28 ins. long, 1 in. in diam. vertically in the ground with top 8 ins. below the surface and with some colored glass bottles and the base of a Coleman lantern buried 1 ft. below the lower end of pipe. S. 0° 06' E., 3 links dist. from corner, set a solid iron pipe 2½ ft. long, 1 in. in diam., 24 ins. in the ground for reference monument, and build a small mound of stone around it.

From the corner of Secs. 14, 15, 22 and 23 the 1/4 Sec. Cor. between Secs. 22 and 23 bears S. 0° 06' E., 39.87 chains dist., marked by the original monument, a limestone 10x12 ins., 10 ins. above ground, marked 1/4 on west face and witnessed as described in the official record.

From the corner of Secs. 14, 15, 22 and 23, the 1/4 Sec. Cor. of Secs. 15 and 22 bears N. 89° 48° W., 39.95 chains dist., marked by the original monument, a limestone 12x8 ins., 10 ins. above ground, marked 1/4 on north face and witnessed as described in the official record.

From the corner of Secs. 14, 15, 22 and 23, S. 89° 53' E. between Secs. 14 and 23, across open field, parallel to road 5 to 20 links north of line, ascend gradual west slope.

- 8.27 Bend in road 20 links N, course W and NE.
- 9.27 Fence corner 17 links N, course E and SE.

Thence along south side of fence, ascending gradual west slope.

- 19.30 Cross fence, course E, along north side fence, ascending gradual west slope.
- 25.05 Cross fence, corner 8 links S, course N and W.
- 26.25 Center of road, course N and S.
- 28.00 Power line, course N and S, ascend steep west slope of cinder hill through heavy growth of pinon and cedar.
- 39.91 1/4 Sec. Cor., Secs. 14 and 23, marked by the original monument, a malpais stone 8x14 ins., 8 ins. above ground, marked 1/4 on north face, and witnessed by the original bearing trees as follows:
 - a pinon 13 ins. in diam. bears N. 26° 55' E., 61 links dist., marked 1/4 S 14 BT
 - a pinon 11 ins. in diam. bears S. 5° 30° E., 31 links dist., marked 1/4 S 23 BT

3.

EXCHANGE SURVEY NO. 676

COCONINO NATIONAL FOREST

STATE OF ARIZONA TO STATE

	Chains	From the corner of Secs. 14, 15, 22and 23, N. 0° 09' W. between Secs. 14 and 15, across open field. Ascend gradual S slope.
•	9.01	Fence corner 50 links W, bears W. and NE, ascend S slope.
	12.00	Enter moderate growth of pinon and cedar timber. Old blazed tree 12 links W of line. Across rocky ground, ascending S slope.
₹.	15.00	Top of ridge, bears NE and SW, across rocky ground, through moderate growth of pinon and cedar, descending gradual N slope.
	17.60	Edge of steep NW slope and rim rock. Leave timber, descend steep NW slope across rocky ground. Drain 170 links W, course N.
	20.00	Along W slope hill. Drain 100 links W, course N, descend NW gradual slope.
	29.08	Top of earth dam 10 ft. high, 60 links W of E end and 200 links E of W end.
	32.00	Along W slope hill. Drain 170 links W, course N, ascend gradual
	10 10 10 10 10 10 10 10 10 10 10 10 10 1	S slope.
	33.00	Enter timber. Ascend steep S slope.
	35•00	Edge of rim rock, top of slope. Drain 200 links W, course NW, descend N slope.
	36.50	Blazed trees to E and W of line.
	37.00	Cross right-of-way fence.
	37.40	Edge of highway fill.
	38.41	S shoulder of new U. S. Highway 66.
	39.31	N shoulder of new U. S. Highway 66.
	39-87	Point for 1/4 Sec. Cor., Secs. 14 and 15, at proportionate distance. Corner falls in slope of new highway fill.
	1003	An uprooted tree marked 1/4 S 14 BT is found in drain about 2 chains to N and W but there is no way to determine its original position.
		Set a wood stake in rock at true point.
	40.67	Set standard U.S.F.S. iron post, 3 ft. long, 1 in. in diam., 24 ins. in ground, for witness monument to 1/4 Sec. Cor., with bronze cap marked:
	ABOORA	S 15 S 14 1947 from which
		1947 from which
		marked WC 1/4 S 14 BT,
•	Corner	a pinon 13 ins. in diam. bears N. 27° 21' W., 287 links dist., marked WC 1/4 S 15 BT,
		a train rail right-of-way marker $2\frac{1}{2}$ ft. above ground on N side of U. S. Highway 66 bears N. 88° 13° E., 110 links dist.
	40.50	S edge of drain, course NE. The transfer to and to the transfer to and the transfer to the tra
	MOTH SE	wolk The point for I/A fee. for doos it and IL, se deberning

EXCHANGE HOMESTEAD XENTRY SURVEY NO. 676

COCONINO NATIONAL FOREST

STATE OF ARIZONA

Chains 43.30	N edge of drain. Ascend S slope.
46.37	Pipe line, course NE and SW, across fairly level ground, through scattered pinon and cedar.
48.03	Track road, course NE and SW.
50.23	Track road, course NE and SW.
51.13	Old road, course NE and SW.
53•71	Blazed trees E and W of line.
58.20	Leave timber, descend N slope.
61.39	Cross S right-cf-way fence, A.T.& S.F.R.R., descend steep N slope.
62.80	Center line westbound track, A.T.& S.F.R.R., course NW and SE.
63.03	Center line eastbound track, A.T.& S.F.R.R., course NW and SE.
64.70	Cross N right-of-way fence, A.T.& S.F.R.R., across open level country.
68.32	S edge Walnut Canyon, course NE and SW. Descend 14' to bottom of canyon.
70-50	N edge Walnut Canyon, course NE and SW. Ascend 14. Thence across level ground.
75.82	S edge Walnut Canyon, course NW and SE. Descend 14' to bottom of canyon.
77-32	N edge Walnut Canyon, course NW and SE. Ascend steep slope.
79•74	Corner of Secs. 10, 11, 14 and 15, marked by the original monument, a malpais stone 12x10 ins., 10 ins. above ground, marked with four notches on S and two on E edges.
d.	N. 89° 58' E, between Secs. 11 and 14 (flag on objective corner visible) over nearly level open land.
2.30	Telephone line, bears SE and NW.
6.58	S edge of U. S. Highway 66, course NW and SE.
7.18	N edge of U. S. Highway 66, course NW and SE.
9•37	Track road, course NW and SE paralleling U. S. Highway 66. Ascend W slope.
13.87	Old road, course NW and SE.
26.00	Enter scattered pinon and cedar timber.
35•10	The point for 1/256 cor. on N bdy. of NE NE NE No. 2 of Exchange Survey No. 676, determined by proportionate measurement, hereinafter described.
38.00	Road bears N and S.
39•97	Center line of railway spur bears N and S.
40.12	The point for 1/4 Sec. Cor. of Secs. 11 and 14, as determined from an original bearing tree.

COCONINO NATIONAL FOREST

STATE OF ARIZONA WIN TO MUNAURA.

5.0

Chains	Set a standard U.S.F.S. iron post 3 ft. long, 1 in. in diam., 30 ins. in ground, with bronze cap marked
eriine. L. in	S11 S14 1947
	New bearing tree, a pinon 13 ins. in diam., bears N. 47° 28' E., 288 links, marked 1/4 S 11 BT.
X98	Thence N. 89° 58' E. Sangli Not to blid 2 me , officers
3.90	Top of ridge, over level ground.
5.40	Track road, bears N and S
9.10	Road, bears NE and SW. Ascend gentle W slope.
9•97	Point for 1/64 Sec. Cor. on N bdy. NW1NE1 Sec. 14 and Corner No. 1 of Exchange Survey No. 676, determined by proportionate measurements.
15.00	Old road, course NE and SW.
18.90	Toe steep W slope. Ascend slope.
25.40	Top of ridge, course N and S. Ancient Indian ruins N and S adjacent to line. Descend E slope.
27.40	Cross head of drain, course S. Ascend steep W slope.
37-90	Top of ridge, bears N and S, across level ground.
39.26	Cross fence, course N and S.
39•89	The corner of Secs. 11, 12, 13 and 14, marked by the original monument, a malpais stone 14x12 ins., 10 ins. above ground, marked with one notch on E and four notches on S face, from which
	original bearing trees:
	a cedar stump, 14 ins. in diam., bears N. 26° E., 93 links dist. Some scribe marks visible.
. Mola W	a pinon, 12 ins. in diam., bears S. 81° E., 114 links dist., marked T 21 N R 9 E S 13 BT.
	Turke Veren, bear a sad 8.
	Subdivision of Section Lines Andrews Section 14
	From the true point for 1/4 Sec. Cor. between Secs. 14 and 15, S. 89° 58' E. on E-W center line.
4.96	Center line of new U. S. Highway 66 (under construction).
9.90	Top of ridge on S edge of deep cut, descend E slope of ridge.
16.00	Enter scattered cedar and pinon, descend E. slope
25.00	Leave timber.
33.90	Edge of S shoulder of new U. S. Highway 66.
35•04	Point for 1/256 Sec. Cor. at proportionate distance. Set temporary corner.

8

COCONINO NATIONAL FOREST

6.	STATE OF ARIZONA NITA TO STATE	
Chains 36.88	Centerline of new U. S. Highway 66. (Course of Contents of the	emano
38.90	Edge of N shoulder of new U. S. Highway 66.	
	Set standard U. S. Forest Service iron post 3 ft. long, 1 in diam., 24 ins. in ground, with bronze cap marked C 1/4 S14	
188	Now bearing tree, a 1740113 das. in diam., seers 1. 17° 232 liaxs, meriod 1/4,3 ll 36.	
	From this point a train rail right-of-way marker 2 ft. at ground, on S side of new U. S. Highway 66 bears S. 2° 02' W. links dist. and a train rail right-of-way marker 2 ft. above on N side of new U. S. Highway 66 bears N. 39° 47' E., 95 li	ground
	From the center 1/4 Sec. Cor., the 1/4 Sec. Cor. of Secs. and 23, bears S. 0° 08' E. and the 1/4 Sec. Cor. of Secs. 11 bears N. 0° 08' W.	and 14
43.00	Top of ridge, descend E slope across open country.	78.8
47.45	Fence, bears N and S.	15.00
50.00	Point for 1/64 Sec. Cor. at proportionate distance,	18.90
adjacent	set an iron pipe, 30 ins. long, 1 in. in diam., 24 ins. i	n ground
(73.77)	Winona Store 5 chains N.	01.8
50.31	Fence, bears N and S	00.77
60.00	Planing mill and lumber ground area. Descend E slope.	39.26
63.25	Centerline railway spur, bears SE.	98.48
66.22	Centerline railway spur, bears SE and NW.	
66.52	Centerline railway spur, bears SE and NW.	
66.94	Centerline westbound track, bears SE and NW.	
69.28	Centerline old road parallel to railroad. Ascend W slope.	
71.58.	Railroad right-of-way fence, bears NW and SE. Ascend steep	W slope.
74.25	Fence, bears N and S.	

74.25

The 1/4 Sec. Cor. of Secs. 13 and 14, marked by the original 79.85 monument, a malpais stone, 14x12 ins., 14 ins. above ground, marked 1/4 on W face and witnessed as described in the official record.

. (noldes denot renam) to Survey of Tract

At point for 1/64 Sec. Cor. on N bdy. NW4NE4 Sec. 14, and Corner No. 1, Exchange Survey No. 676, set a standard U. S. Forest Service iron post, 3 ft. long, 1 in. in diam., 24 ins. in ground, with bronze cap marked

from which

a pinon, 11 ins. in diam., bears S. 5° 33' E., 152 links dist., marked 1 ES 676 BT.

MONASTEANXENNEX SURVEY NO. 676

COCONINO NATIONAL FOREST

STATE OF ARIZONA

	STATE OF ARIZONA 7.
Chains	a pinon 8 ins. in diam., bears S. 36° 10° W., 411 links dist., marked 1 ES 676 BT.
nothin	S. 89° 58' W., along N bdy. of tract.
9-97	The 1/4 Sec. Cor. between Secs. 11 and 14.
14.99	The point for 1/256 Sec. Cor. on N bdy. of NE1NE1NW1 Sec. 14 and Corner No. 2 of Exchange Survey No. 676.
	set a standard U. S. Forest Service iron post, 3 ft. long, 1 ins. in diam., 28 ins. in ground, with bronze cap marked
	S 11 2 ES 676 from which
	a pinon lli ins. in diam. bears S. 81° 24' E., 169 links dist., marked 2 ES 676 BT
- 0	marked 2 ES 676 BT
	S. 0° 09' E. along W bdy. of tract. Descend over SW slope.
1.37	Road, bears NE and SW.
15.05	Centerline of U. S. Highway 66, bears NW and SE.
24.74	Fence on N side of right-of-way.
	Point for Corner No. 3, Exchange Survey No. 676. On N bdy. of A.T.& S.F.R.R. right-of-way.
in agais	Set a standard U. S. Forest Service iron post, 3 ft. long., 1 in. in diam., 28 ins. in ground, with bronze cap marked 3 ES 676
b.	ary to end far a made of 1947 tindo 78.0 142 °07 from which
	a pinon 28 ins. in diam., bears N. 71°.14! W., 529 links dist., marked 3 ES 676 BT
	From this point, the temp. 1/256 Sec. Cor. on E-W centerline bears S. 0° 09' E. 15:12 chains dist.
2)	Thence along bdy. of A.T.& S.F.R.R. right-of-way,
16.C*	N. 86° 36' iE. forms of out of enit to seed to Jes do man
	Train rail marker 3 ft. high, and point for Corner No. 4, Exchange Survey No. 676.
	Alongside marker, set a standard U. S. Forest Service marker iron post 3 ft. long, 1 in. in diam., 24 ins. in ground, with bronze
doing	cap marked 4 ES 676 4 1947
ednii i	N. 30 124 W a crand narray yawate-Jagin lian miant a
1.51	Train rail marker 3 ft. high and point for Corner No. 5, Exchange Survey No. 676.

Alongside marker, set a standard U. S. Forest Service iron post 3 ft. long, 1 in. in diam., 24 ins. in ground, with bronze cap marked

Tran brue noint for corner

.josaj lo .ybd & sabis ... 'Yo 'C E

10

STATE OF ARIZONA

6.013

noti amman

Chains of the ... tor on . 5 Es 676 als Mi .ani C month

COCONINO NATIONAL FOREST

from which

a pinon 16 ins. in diam., bears N. 85° 58° E., 394 links dist., marked 5 ES 676 BT 1 296 Sec. Cor. on

a pinon 26 ins. in diam., bears N. 9° 51' E., 466 links dist., marked 5 ES 676 BT

N. 86° 36' E. .

fence

Train rail marker 3 ft. high 6 links N. 1.51

End of tangent, fence 4 links N of line. 2.87

Thence on long curve by traverse, as follows:

N.87° 06', E., 0.81 chains Fence 3 links N of line

N. 88° 06' E., 0.82 chains

2

in diem., 28 ins. in

N. 89° 36' E., 0.87 chains

S. 88° 24' E., 0.87 chains

Cross fence

S. 86° 24' E., 0.87 chains

S. 84° 24' E., 0.87 chains

S. 82° 24' E., 0.87 chains Ascend W slope highway fill

S. 80° 24! E., 0.87 chains Wedge U. S. Highway 66

S. 78° 24' E., 0.87 chains

Cross hgwy. Descend E slope of fill.

S. 76° 24' E., 0.87 chains

Descend E slope of field

S. 74° 24! E., 0.87 chains E track railway spur

S. 72° 24' E., 0.87 chains

S. 70° 24' E., 0.32 chains Point for Corner No. 6, Exchange Survey No. 676

This point falls in road where monument cannot be established. Cannot set witness on line to N due to gravel pit.

.T.s G.F.R.E. right-of-w

S. 0° 07° E., 80 links dist., set a standard U. S. Forest Service iron post 3 ft. long, 1 in. in diam., 24 ins. in the ground, for witness corner, with bronze cap marked

> . WC 6 ES 676

> > 1947

from which

a train rail right-of-way marker bears S. 81° 19' E., 301 links Sit. hish and noint

centerline railway spur bears S. 50° W., 23 links dist.

From true point for Corner No. 6, the 1/64 Sec. Cor. on E-W centerline bears S. 0° 07' E., 15.54 chains dist.

From true point for corner

N 0° 07' W., along E bdy. of tract.

EXCHANGE XHOMESURADX XHOTEXX SURVEY NO. 676

COCONINO NATIONAL FOREST

STATE OF ARIZONA TO STATE

			7.
	Chains 0.94	S edge of gravel pit.	Cha
•	6.94	N edge of gravel pit and top of ridge, descend N slope.	
	7.94	Road, bears NW and SE.	
	9.94	Old road, bears NW and SE.	
	11.94	Enter scattered pinon and cedar timber.	
	24.35	To Corner No. 1, Exchange Survey No. 676, the place of beginning.	
		This tract includes the $W_{2}^{1}NW_{4}^{1}NE_{4}^{1}$, $E_{2}^{1}E_{2}^{1}NE_{4}^{1}NW_{4}^{1}$, the portion of t $NW_{4}^{1}SW_{4}^{1}NE_{4}^{1}$ and $NE_{4}^{1}NE_{4}^{1}SE_{4}^{1}NW_{4}^{1}$, lying N of the A.T.& S.F.R.R. right-way, in Sec. 14, T. 21 N., R. 9 E., containing 35.11 acres.	the of-

Form 85. Sheet No. 2. HOMESTEAD ENTRY SURVEY NO.

NATIONAL FOREST

Chains Only a solds of movel as the sold top of riego, descend a sign of the sold as a sold aso		NATIONAL FOREST		
Chains 0.94 % edge of gravel pit. 6.91 , edge of gravel pit and top or ridge, descent M slape. 7. 'I hose, hears NW and SE. 9. 'I old road, bears NW and SE. 11. 'H, anter sow tered pinon and season tinter. 24.55 To horner No. 1, Etenange durvey W. (TE, the pisce of begin ing. This treat includes the shapely, wishing in the portion of the way, in sec. iii, T. Elegat, thing N of the interest.	, p	STATE OF APPLIEN TO ETATE		
6.94 seage of gravel pit and top or riage, descond a slape. 7.04 hoar, bears NM and SE. 9.44 Old road, bears NM and SE. 11.94 anter goattered pinon and adam timber. 24.55 To Garner We. 1, Exensage Lurvey W. Olf, the place of begin ing. This tract includes the samples, wiether NM; the portion of the MM; signify and Whit Course, tring I of the L. C. C. T. The tot-of-way, in Sec. 14, 7.21	1		on final	
7. Le Hoad, bears EW and SE. 9. Le Old road, bears EW and SE. 11. Le anter souttered plaon and actar timber. 24. He To Corner No. 1, Exensing Jurvey W. (Th. the plate of Demin ing. This tract includes the ENWYNN, Richards, the portion of the E. S.	OHG HIS	Seding of gravel pat.		
7. Le Hoad, bears EW and SE. 9. Le Old road, bears EW and SE. 11. Le anter souttered plaon and actar timber. 24. He To Corner No. 1, Exensing Jurvey W. (Th. the plate of Demin ing. This tract includes the ENWYNN, Richards, the portion of the E. S.		ace of gravel wit and top of glage, descend of aleps-	10.3	
9. Ut Old road, bears WW and Sh. 11. Sh. dater southered pinon sad ander timber. 24.55 To Carner No. 1. Erensunge darvey V. (76, the place of beginning. This tract includes the MANAPANE, the portion of the Majorian of the Majorian and the Majorian Sh. S. (1). The tract of the Majorian Sh. (1). The tract of the J. (1). The contenting Sp. 11 cares.				
11.54 ander scattered pigon and seder timber. 24.55 To Sorner No. 1. Erenange Anresy No. (Th. the place of begin ing. This tract includes the WANNSHME, Missen No. the portion of the Missignes and Wilderson the Ling N of the Local timber of the way, in Sec. 11, T. 21 N. 9 F., Sontenning 55.11 cares.			Lar Section	
24.35 to normer No. 1. Erensuge invery No. 676, the pister the nervisor of the Misters of the portion of the Misters of the Mi			I Base III	
This tract includes the sales, agains, the postice of the English				
M. S. S. M. See. 14. T. 21 N. S. S. S. S. Southerning 59.11 Eures.			77.1	
	= 10+J sts	kt . C. A. W. o f. L. L. ear to I gury L. Jaky Con Distribute games a way		
				•

Directions.—1. Carry out tin area in acres to three decimals, and all other calculations to two decimals only.

2. In balancing the latitudes and departures do not obliterate or change the original figures, but put the corrections above in red ink.

3. See Chapter IX, Manual of 1930, for instructions relative to balancing the closing error, computation of areas, and use of total latitudes and departures.

TABLING AND CALCULATIONS OF EXCHANGE SURVEY NO. 676

No.	COURSE	DISTAL	NCE		LATI	TUDES		DE	PAR	TURES		DOUBLE MERIDIAN DISTANCE	NORTH AREAS	AREAS SOUTH AREAS		TOTALS	
				Non	тн	South	I	East		West					LATITUDE	DEPARTURE	
						CLOSUR	e of 1	WEST 5/8	OF	N/2 SEC.	14,	T. 21 N., R.	9 E.				
4 Cor., Se	ec. 14, T. 21 N., R.	9 E.			= 12												
	N. 00 09 W.	39	87	3	9 87					0	10						
Sec. Cor.,	Sec. 14, T. 21 N.,	R. 9 E															
	N. 89° 58° E.	50	09		03			50	09	6 7 × 1							
pt. N bdy	$NW_4^2NE_4^2$ Sec. 14, T	21 N.	, R.	9 E.			1 (1								
	S. 00 07 E.	39	89			39	89		08								
pt. S bdy	SWINE Sec. 14, T	. 21 N.	, R.	9 El													
	N. 890 581 W.	50	00		03					50	00						
Cor., Se	ec. 14, T. 21 N., R.	9 E.															
	1.5.6	179	85	3	9 93	39	89	50	17	50	10						
	The Following Commence				9 89	11 1 1		50									
					Ojt	· II			07								
	Closing error - 1	/2231															
									. 7								
				0 0												Become	
																1	
	1																
			1														

APPROVAL

DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
PUBLIC SURVEY OFFICE

Phoenix, Arizona October 21, 1947

The foregoing field notes of EXCHANGE SURVEY No. 676,

executed by Aaron F. Jones, Civil Engineer,
Forest Service, under his special instructions,
dated April 23, 1947, having been critically
examined, and the necessary corrections and
explanations made, the said field notes, and
the surveys they describe, are hereby approved.

Frank W. Chapin Office Cadastral Engineer.

UNITED STATES

DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT GENERAL LAND OFFICE

CADASTRAL ENGINEERING SERVICE
PUBLIC SURVEY OFFICE

103 U.S. Court House Phoenix, Arizona

April 23, 1947

SPECIAL INSTRUCTIONS

EXCHANGE SURVEY NO. 676

Township 21 North, Range 9 Bast,

Cila and Salt River Meridian.

Office authority for the issuance of Special Instructions for the necessary field work of this survey is contained in Bureau of Land Management decision dated March 21, 1947.

Method of Procedure

Retrace the line between Secs. 11 and 14. On this line at a point determined by proportionate measurement, establish the 1/64 sec. cor. at midpoint of north boundary of NWANEA Sec. 14. Also on this line, establish the 1/256 sec. cor. at midpoint of the north boundary of NEANEANWA Sec. 14.

Determine the center of section 14 at intersection of north-south and east-west center lines. At one-fourth the distance from center 4 sec. cor. to the 4 sec. cor. of secs. 13 and 14, set temp. 1/64 sec. cor. From this point run true line northerly to the 1/64 sec. cor. established between secs. 11 and 14. At intersection with north boundary of railroad right-of-way, establish the southeast corner of the selection. At one-eighth the distance from the center 4 sec. cor. to the 4 sec. cor. of secs. 14 and 15, set temp. 1/256 sec. cor. From this point run true line northerly to the 1/256 sec. cor. established bet. secs. 11 and 14. At intersection with the north boundary of the railroad right-of-way establish the southwest corner of the selection.

This area may be divided into two tracts by the establishment of a common corner at the intersection of the north-south center line of sec. 14 and north boundary of the railroad right-of-way.

Having established the limiting corners, the survey of the boundaries of the selected lands will be completed.

The corner monuments will consist of iron posts and be appropriately marked.

General

In addition to these special instructions, the Manual of Land Surveying will be the guide for all technical procedure.

Upon completion of the field work, the field notes of the survey will be prepared in triplicate which along with a plat of the survey drawn to scale, will be mailed to the Public Survey Office at Phoenix for checking and approval.


Should conditions arise appearing to demand additional instructions or which apparently make these special instructions inapplicable as prepared, the chief of field party will be expected to submit a report of the situation with such recommendations as may be responsive to the authorization.

This survey will be designated as EXCHANCE SURVEY No. 676.

Frank W. Chapin Office Cadastral Engineer.

Approved: / 25 /927

Director.



UNITED STATES
DEPARTMENT OF THE INTERIOR
Bureau of Land Management
Washington 25, D.C.

Mar 21 1947

DECISION

Atchison, Topeka and Santa Fe Railway Company Coconino National Forest Forest Exchange
Land for Land

2115293 "K" (Phoenix)

Conditional Approval

On July 2, 1946 the Assistant Secretary of Agriculture recommended favorable consideration by this Department of a proposed exchange with the Atchison, Topeka and Santa Fe Railway Company, 121 East Sixth Street, Los Angeles 14, California, of land within the Cosonino National Forest, Arizona, for land within the same forest, pursuant to the act of March 20, 1922 (42 Stat.465) as amended by the act of February 28, 1925 (43 Stat 1090,16 U.S.C. secs. 485, 486).

The applicant offers the SE $\frac{1}{4}$ sec. 15, lots 15,22, sec. 27, T. 19 N., R. 6 E., G.& S.R.M., Arizona, 239.55 acres. In exchange for the offered land the applicant selects the $E_2^{\frac{1}{2}}SW_4^{\frac{1}{4}}$, $W_2^{\frac{1}{2}}SE_4^{\frac{1}{4}}$ sec. 2, $E_2^{\frac{1}{2}}NW_4^{\frac{1}{4}}$, $W_2^{\frac{1}{2}}NE_4^{\frac{1}{4}}SW_4^{\frac{1}{4}}$, $E_2^{\frac{1}{2}}NE_4^{\frac{1}{4}}SW_4^{\frac{1}{4}}$, $E_2^{\frac{1}{2}}SE_4^{\frac{1}{4}}SW_4^{\frac{1}{4}}$, $NW_4^{\frac{1}{4}}SW_4^$

The offered land is subject to easements which may not be of record and to reservations contained in United States patents.

The SE4 sec. 15, T. 19 N., R. 6 E., is subject to an easement for right-of-way for National Forest Highway No. 7, U.S. Alternate No. 89, outstanding in the State of Arizona, or County of Coconino, and to a lease for a rearing pond outstanding in the Fish and Game Department of the State of Arizona.

A reservation of the fissionable source materials will be made by the United States in the selected land in accordance with the act of August 1, 1946 (Public Law 535, 79th Congress).

The selected land is subject to a reservation to the United States of an easement and right-of-way for United States Highway No. 66 as now located and defined, and the right of the United States, its officers, agents, or employees to maintain, operate, repair or improve the same as long as needed or used for or by the United States.

2115293 "K" (Phoenix)

Land survey instructions should be requested by the Forest Service of the Public Survey Office to identify on the ground the two selected tracts in the W½NW¼NE¼, NW¼SW¼NE¼. N½SW¼SW¼NE¼, E½NE¼NW¼, E½NE¼SE¼NW¼, NE¼SE¼SE¼NW¼ sec. 14, T. 21 N., R. 9 E., and to establish the area of these tracts.

The Assistant Secretary of Agriculture states that the public interest will be benefited by the exchange, that the offered land is valuable chiefly for national forest purposes, unoccupied by adverse claimants, and that the lands selected in the exchange do not exceed the offered land in value, due consideration having been given to the above mentioned reservations.

In view thereof, and as there are no apparent objections, the proposed exchange is hereby approved, subject to the submission of acceptable title to the offered land, compliance with the law and regulations, and to any intervening valid objections.

The applicant should submit a recorded general warranty deed of conveyance to the United States, which deed should recite that the consideration for the conveyance is the exchange therefor of land not greater in value than the offered land, and there should be made a reference to the acts of Congress under which the exchange is made. Revenue stamps in the amount of \$11.00 should be affixed to the deed and canceled.

As the lands in this exchange are located in Coconino County, the Acting Manager is directed, in issuing his order for publication, to designate The Coconino Sun at Flagstaff as the medium of publication.

The applicant is allowed sixty days from receipt hereof within which to file a formal application with the Acting Manager of the District Land Office at Phoenix, Arizona, and all other papers required by the regulations, paragraphs 148.5 to 148.14 inclusive, Circular No. 863e, copy attached.

(sgn) Fred W. Johnson

Director

Approved: Mar. 21, 1947 (sgd) G. Girard Dauder

Assistant Secretary of the Interior.

Attachments.