

**M
S
-**

0

1

7

4

9

7/10/03

(4-683.)

Mineral Survey No. 1749 amended

Lot No. _____

Gila

Land District.

FIELD NOTES

OF THE SURVEY OF THE MINING CLAIM OF

Solomon Springs Copper Co
by H. C. H. Palmer, Authorized Agent

KNOWN AS THE

Paris and Promise

Warren

Mining District,

Cochise County, Arizona

Section 31 + 32, Township 23 S, Range 25 E. 4 + 5. R. B + M

Surveyed under instructions dated July 2, 1903.

by Geol. Clark,
U. S. Deputy Mineral Surveyor.

Claim located June 13th, 1903
Survey commenced July 7th, 1903
Survey completed July 8th, 1903

o 6-100

Claimants Address

Busbee, Cochise County Arizona

PRELIMINARY OATHS OF ASSISTANTS IN SURVEY OF MINING CLAIM.

WE, H. D. Hannah and D. L. Smith,
do solemnly swear that we will well and faithfully execute the duties of chain carriers; that we will level the chain upon even and uneven ground and plumb the tally-pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we assist in measuring, to the best of our skill and ability, and in accordance with instructions given us, in the survey of the Mining Claim of Solomon Sprin
Copper Co
known as the Paris + promise
situate in Warren mining district
Cochise County, Arizona
in Section 31+32, Township No. 23S, Range No. 25E, G + S. R. B + m

H. D. Hannah, Chairman.
D. L. Smith, Chairman.

Subscribed and sworn to by the above-named persons before me this 6th day of July, 1903

J. M. Osborne
Notary Public in and for the County
of Cochise, Territory of Arizona.

I, _____, do solemnly swear that I will well and truly
perform the duties of axman, in the establishment of corners and other duties, according to instructions given me and to the best of my skill and ability, in the survey of the Mining Claim of

known as the _____
more fully described in the preceding affidavit.

_____, Axman.

Subscribed and sworn to by the said _____
_____ before me this _____ day of
_____, 190____

I, _____, do solemnly swear that I will well and truly
perform the duties of flagman, in the establishment of corners and other duties, according to instructions given me and to the best of my skill and ability, in the survey of the Mining Claim of

known as the _____
more fully described in the preceding affidavit.

_____, Flagman.

Subscribed and sworn to by the said _____
_____ before me this _____ day of
_____, 190____

Paris Lode.

Feet.

1749.

- Beginning at cor. No. 1 N.W. cor. identical with locat.
A pine post 4 ft. long 4 in. sq. set in the ground in a mound of stones scribed 1-1749 P.L.
Whence a rock in place 2 X 2 X 3 ft. chiseled X1-1749 B.R. brs. n. 36° 45' E. 130.00 ft. and the N.W. cor. sec. 32 township 23S. range 25 E. G&SRB&M brs. N. 50° 20' E. 149 ft.
- Thence S. 66° 22' E.
- 125.2 To intersection W. side line sec. 32 and E side line sec. 31 township 23 S. range 25 E. G&SRB&M at S. 145. 25 ft. from N.W. cor. sec. 32 ~~at~~ *N 51 34 7 ft from S.W. cor.*
- 1500.00 Same bearing to cor. No. 2 to N.E. cor identical with locat
A pine post 4 ft. long 4 in. sq. set 1 ft. in the ground in a mound of stones scribed 2- 1749 P.L.
Whence a rock in place level with surface 2 ft. sq. chiseled X2- 1749 B.R. brs. N. 89° 30' W. 66 ft.
- Thence S. 33° 40' W.
- 300.00 To a pine post in the ground ~~in~~ a mound of stones identical with the locat. for E. end center.
- 600.00 Same bearing to cor. No. 3 SE. cor., identical with locat. (~~in~~) a pine post 4 ft. long, 4 in. sq. set 1 ft. in the ground in a mound of stones and scribed 3- 1749 P.L.
Whence a rock in place 1 ft. high 2 ft. sq., chiseled X3 - 1749 B.R. brs. N. 1° 56' W. 87.3 ft.
- Thence N. 66° 22' W.
- 1011.8 To intersection W. line sec 32 township 23 S range 25 E, at S/ 790.1 ft. from the north west cor. ~~at~~ *N 44 59.9 from the S.W. cor.*
- 1094.1 Same bearing to intersection 23 promise lode of this survey at S/ 17° 52' W. 19.2 ft. from cor. No. 2
- 1500.00 Same bearing to cor No. 4 S.W. cor. identical with locat. and with cor. No. 5 promise lode of this survey
A pine post 4 ft. long 4 in. sq. set 1 ft. in the ground in a mound of stones and scribed 4- 1749 P.L.
Whence a rock in place , level with surface 2 X 3 ft. chiseled X4 -1749 B.R. brs. N. 87° 10'E. 49.5 ft.
- Thence N 33° 40' E.
- 178.00 To cor. No. 1 promise lode of this survey

300.00	Same bearing to a pine post in a mound of stones, identical with ^o location for west end center
600.00	Same bearing to cor. No. 1 the place of begining
	LEDGE
	The presumed course of the ledge on this claim , as nearly as can be determined from present development is from the E. end center of location N 66° 22W 1500.00 ft.
	PROMISE LODE.
	Begining at cor. No. 1 N.W. cor. <i>on line 4-1 of Paris lode of this survey</i> A pine post 4 ft long 4 ins. sq. set 1 ft. in the ground in a mound of stones and scribed 1-1749 Pr.L.
	Whence a rock in place 1 X 1 X 2 ft. , chiseled X1-1749 B.R. brs. N. 16° 54' E. 103 ft. and original o location brs. N 43° 35' W. 56 ft. and NE. cor. sec. 31 and the NW. cor. sec. no. 32 township 23 S. range 25E. G&SRB&M brs. N. 38° 01' E. 568.4 ft.
	Thence S 43° 39' E.
240.00	To mound of stones identical with locat. N. end center
404.4	Same bearing to cor. No. 2 N.E. cor. identical with locat. a pine post 4 ft. long 4 in. sq. set 1 ft. in the ground in a mound of stones and scribed 2- 1749 Pr.L. Whence a rock in place 2 ft. sq. 6 in. high chiseled X2- 1749 B.R. brs. N. 3° 5' W. 25.5 ft.
	Thence S 17° 52' W.
19.2	To intersection Paris Lode of this survey at S. 66° 22' E. ^{403.9ft.} from cor. No. 4 on line 3-4
894.90	Same bearing to cor. No. 3 the SE. cor. , identical with locat. , a pine post 4 ft. long, 4 in. sq. set 1 ft. in the ground in a mound of stones & scribed 3-1749 Pr.L. Whence a rock in place 1X 2 X 3 ft/ chiseled X3- 1749 B.R. brs. N. 56° 18' E. 44.6ft.
	Thence N 43° 39' W.
320, 70	To mound of stones , identical with locat. fo S. end center
423.00	Same bearing to junction of washes 20 ft. wide, 5 ft. deep, course of washes SE.

FEET.

643.5 Same bearing to cor. No. 4 S.W. cor. identical with locat. a pine post , 4 ft. long 4 in. sq. 1 ft. in ground in a mound of stones and scribed 4-1749 Pr. ↓ Whence a rock in place 1 X 1 X 2 ft. chiseled X4-1749 B.R. brs. N. 27° 15' E. 55.6 ft.

Thence N. 32° 44' E.

630. 7 To cor. No. 5
A pine post 4 ft. long 4 in Sq. etc. identical with cor. No. 4 Paris Lode, a claim of this survey , scribed 5-1749 Pr.L.

Thence N 33° 40' E.

178.00 To cor. No. 1 the place of begining

LEDGE

,The presumed course of the ledge on this claim as nearly as can be determined from present development is from the S. end center N. 17° 52' E. 894.9 ft.

IMPROVEMENTS.

I certify that the value of the labor and improvements on these claims is not less than 500.00 dollars on each claim thereof and that said improvements placed thereon by the claimants or their grantors consist of:-

PARIS LODGE.

No. 1. discovery tunnel 4 X 7 X 60 ft. course S. 66° E. brs. from cor. No. 4 N. 84° 42' E. 857 ft.

Value \$ 500.00

No. 2. Tunnel 4 X 6 X 40 ft brs. from same point N. 87° 27' E.

850 ft. Value \$ 400.00

Total improvements Paris Lode \$900.00

PROMISE LODGE.

No. 1. Discovery Shaft brs from cor No. 2 S 73° 54' W.

263 ft. 4X6X15 ft. Value \$150.00

No.2. Shaft 4X6X20 ft. brs. from cor. No. 3 N. 17° 30' W.

260 ft. Value \$ 240.00

No. 3. Open Cut 4x20x10 ft course S/ 86° W. brs. from cor.

No. 4 S. 86° 15' E. 170 ft. value \$ 160.00

Total Improvements Promise Lode \$550.00

Total Improvements on Group \$ 1450.00

-----OTHER IMPROVEMENTS-----

Center of S. end of one story frame house facing
S. brs from Cor No.4, Paris Lode N.87°27'E. 750 ft.

FEET.

AREA.

Total Area Paris Lode	20.345A.
Less area in conflict with promise Lode of this survey	0.895A.
Net Area Paris Lode	19.45 Acres
Total and Net Area Promise Lode	9.483 A. ✓
Net Area of Group	28.933 A.

ADJOINING CLAIMS.

North Claims and owners unknown
 East Pritchards claim names unknown J.G. Pritchard owner.
 South Manila and Center claims owned by applicants herein.
 West Claims and owners . unknown

LOCATION.

These claims are located in the N.W. quarter sec. 32. ~~5~~ the N.E. cor. sec. 31. township 23 S. range 25 E. G&SRB&M.

Instrument.

The survey was made with a Gurley Light Mountain Transit. The courses were deflected from the true Meridian was determined by Solar observations, checked by an observation on Polaris. All distances were measured with a 300 ft. steel tape

Bisbee Arizona,

Geo. C. Clark

July 8th 1903. U.S. Deputy Mineral Surveyor.

FINAL OATHS FOR SURVEYS.

LIST OF NAMES.

A list of the names of the individuals employed by Geo. C. Clark
 United States Deputy Mineral Surveyor, to assist in running, measuring, and marking the lines
 corners and boundaries described in the foregoing field notes of the survey of the mining claim
 of Solomon Springs Copper Co
 known as the Paris + Promise
 and showing the respective capacities in which they acted.

H. D. Hannah , Chairman.
D. L. Smith , Chairman.
 , Assn.
 , Flagman.

FINAL OATHS OF ASSISTANTS.

We, H. D. Hannah
 and D. L. Smith , do solemnly swear that we assisted
Geo. C. Clark , United States Deputy Mineral Surveyor, in marking the corners and
 surveying the boundaries of the mining claim of
Solomon Springs Copper Co by
H. C. H. Palmer, Authorized Agent known as the
Paris + Promise , represented
 in the foregoing field notes as having been surveyed by said deputy mineral surveyor and under
 his direction; and that said survey has been in all respects, to the best of our knowledge and
 belief, faithfully and correctly executed, and the corner and boundary monuments established
 according to law and the instructions furnished by the United States Surveyor-General for
Arizona

H. D. Hannah , Chairman.
D. L. Smith , Chairman.
 , Assn.
 , Flagman.

Subscribed and sworn to by the above-named persons before me
 this 8th day of July, 1903

J. M. Hornell
 Notary Public in and for the County
 of Cochise, Territory of Arizona.
 My Commission expires Jan. 9 1904

FINAL OATH OF U. S. DEPUTY MINERAL SURVEYOR

I, Geo. C. Clark, U. S. Deputy Mineral Surveyor, do solemnly swear that, in pursuance of instructions received from the United States Surveyor General for Arizona, dated July 2nd 1903, I have, in strict conformity to the laws of the United States, the official regulations and instructions thereunder, and the instructions of said Surveyor General, faithfully and correctly executed the survey of the Mining Claim of Polomon Springs Copper Co Paris & Promise, known as the _____, situate in Warren Mining District, Cochise County, Arizona in Section 31 & 32, Township No. 23 S, Range No. 25 E. Gr S. R. B & M and designated as Survey No. 1749, as represented in the foregoing field notes, which accurately show the boundaries of said mining claim as distinctly marked by monuments on the ground, and described in the attached copy of the location certificate, which was received by me from the Surveyor General with said instructions, and that all the corners of said survey have been established and perpetuated in strict accordance with the law, official regulations and instructions thereunder; and I do further solemnly swear that the foregoing are the true and original field notes of said survey and my report therein, and that the labor expended and improvements made upon said mining claim by claimant or their grantors are as therein fully stated, and that the character, extent, location and itemized value thereof are specified therein with particularity and full detail; and that no portion of said labor or improvements so credited to this claim has been included in the estimate of expenditures upon any other claim.

Geo. C. Clark
U. S. Deputy Mineral Surveyor.

Subscribed and sworn to by the said Geo. C. Clark
U. S. Deputy Mineral Surveyor, before me _____
this 5th
day of July 1903

J. M. McConnell
Notary Public in and for the County
of Cochise, Territory of Arizona
My Commission expires Jan. 9 1904

Affidavit of Five Hundred Dollars Improvements.

We, H. W. Hannah, and D. J. Smith

of lawful age, being first duly sworn according to law, depose and say: That we are acquainted with the Paris + Promise mining claim, situate in Wureu Mining District, Cochise County, Arizona Territory, for which Salomon Spring Co Copper Co. by H. C. H. Pollock, authorized agent has made application for survey prior to application for patent under the provisions of the Act of Congress, approved May 10, 1872; and that the labor done and improvements made thereon by the applicants and their grantor exceed Five Hundred Dollars in value, and further, that we are not personally interested in said mine.

H. W. Hannah

D. J. Smith

TERRITORY OF ARIZONA,

County of Cochise } ss:

Sworn to and subscribed before me, this 8th

day of July, 1903

J. M. O'Connell

Notary Public in and for the County of Cochise, Territory of Arizona. My Commission expires Jan. 9 1904

AMENDED

NOTICE OF MINING LOCATION.

LODE CLAIM.

TO ALL WHOM IT MAY CONCERN:

This mining claim, the name of which is the Promise Mining Claim, situate on lands belonging to the United States of America, and in which there are valuable mineral deposits, was entered upon and located for the purpose of exploration and purchase, by the Solomon Springs Copper Company, a corporation organized under the laws of Arizona, the undersigned, on the 13th day of June, 1903.

The length of this claim is 800 feet, and we claim 105 feet in a northeasterly direction, and 695 feet in a southwesterly direction, from the center of the discovery shaft at which this notice is posted, lengthwise of the claim, together with 300 feet in width of the surface ground, on each side of the discovery monument of said claim. The general course of the lode deposit, and premises, is from northeasterly to southwesterly.

The claim is situated and located in the Warren Mining District, in Cochise County, in the Territory of Arizona, about 1-3/4 miles in a northeasterly direction from Solomon Springs, and adjoining the Center Claim on its east side-line.

The surface boundaries of the claim are marked upon the ground as follows: Beginning at a monument of stones, at a point in a northeasterly direction, 105 feet from discovery shaft at which this notice is posted, being the center of the northeasterly end line of the claim. Thence 188 feet northwesterly to a monument of stones, being the northerly corner of said claim. Thence southwesterly 800 feet to a monument of stones, being at the westerly corner of said claim. Thence southeasterly 300 feet to a monument of stones, the center of the southwesterly end line of said claim. Thence southeasterly 500 feet to a monument of stones, (the center of the southwesterly end line of said claim.) Thence southeasterly 300 feet to a monument of stones, being at the southerly corner of said claim. Thence northeasterly 800 feet to a monument of stones, at the easterly corner of said claim. Thence northwesterly 188 feet to the place of beginning.

All done under the provisions of Chapter Six, of Title XXXII, of the Revised Statutes of the United States, and an Act of the General Assembly of Arizona, entitled "An Act to Revise and Codify the Laws of the Territory of Arizona," approved March 16th, 1901.

This is an Amended Location Notice of the Promise Mining claim, located by the Solomon Springs Copper Company, on the 9th day of June 1902, and recorded in Book 20, Records of Mines, page 543, in the office of the County Recorder of the aforesaid county of Cochise, to which reference is hereby made, and this Amended Location Notice is made and posted to correct errors in the description of the said original location notice.

Dated and posted on the ground this 13th day of June, 1903.

Solomon Springs Copper Company,
by H. C. H. Palmer, Agent.

Filed and recorded at request of S. E. Hazzard June 13th, A D 1903 at 2 p. m. Book 26 Record of Mines page 331.

Territory of Arizona,)
County of Cochise.) ss.

I, Frank Hare, County Recorder in and for said county hereby certify that I have compared the foregoing copy with the original Amended Location Notice of the Promise Mining claim filed and recorded in my office on the 13th day of June, A D 1903 Book 26 Record of Mines page 331. and that the same is a full, true, and correct copy of such original and of the whole thereof.

Witness my hand and official seal the 13th day of June, 1903.

Frank Hare

County Recorder.

AMENDED

Notice of Mining Location.

LODE CLAIM.

To All Whom It May Concern:

This mining claim, the name of which is the Paris Mining Claim, situate on lands belonging to the United States of America, and in which there are valuable mineral deposits, was entered upon and located for the purpose of exploration and purchase by the Solomon Springs Copper Company, a corporation organized under the laws of Arizona.

(Locator must insert either "a citizen of the United States," or, "who has declared his intention to become a citizen of the United States.") the undersigned, on the 13th day of June 1903.

The length of this claim is 1500 feet and none claim 475 feet in a north westerly direction, and 1025 feet in a south easterly direction from the center of the discovery shaft, at which this notice is posted, lengthwise of the claim, together with 300 feet in width of the surface grounds, on each side of the discovery monument of said claim. The general course of the lode deposit and premises is from the easterly to the westerly.

The claim is situated and located in the Warren Mining District, in Cochise County, in the Territory of Arizona, about one mile in a northerly direction from Solomon Springs and about 2000 feet in a southeasterly direction from the El Paso mining claim.

The surface boundaries of the claim are marked upon the ground as follows: Beginning at a monument of stones being at the center of the westerly end line of the claim, at a point in a north westerly direction 475 feet from the discovery shaft (at which this notice is posted), being in the center of the westerly end line of said claim; thence southerly 300 feet to a monument of stones, being ^{at} the southwesterly corner of said claim; thence easterly 1500 feet to a monument of stones, being at the southeasterly corner of said claim; thence northerly 300 feet to a monument of stones at the center of the easterly end ^{line} of said claim; thence northerly 300 feet to a monument of stones, being at the northeasterly corner of said claim; thence westerly 1500 feet to a monument of stones being at the northwesterly corner of said claim; thence southerly 300 feet to place of beginning.

All done under the provisions of Chapter Six, of Title XXXII, of the Revised Statutes of the United States, and an Act of the General Assembly of Arizona, entitled "An Act to Revise and Codify the Laws of the Territory of Arizona," approved March 16, 1901.

This is an Amended Location Notice of the Paris Mining Claim, located by A. K. Campbell on the 1st day of January 1901, and recorded in Book 13 of Records of Mines, at page 276 in the office of the County Recorder of the aforesaid County of Cochise to which reference is hereby made, and this Amended Location Notice is made and posted to correct errors in the description in the said original Location Notice.

Dated and posted on the ground this 13th day of June 1903.
Solomon Springs Copper Co
by N. C. H. Palmer, Auth. Agent

ed and recorded at request of S. C. Hazzard June 13th A.D. 1903 at 2 P.M.
K 26 Record of mines page 326.

Territory of Arizona,)

:SS.

13

County of Cochise.)

I, Frank Hare County Recorder in and for said County, hereby certify that I have compared the foregoing copy with the original amended location notice of the "Paris" mining claim, filed and recorded in my office on the 13th day of June 1903, in Book 26, page 326, Record of Mines, and that the same is a full, true and correct copy of such original and of the whole thereof.

Witness my hand and seal of office, this 15th day of July, 1903.

Frank Hare

County Recorder.

TERRITORY OF ARIZONA,
 County of..... } ss.

I,....., County Recorder in and for the County and Territory aforesaid, do hereby certify that the within instrument was filed for record at..... o'clock..... M., on this..... day of..... 190..., and duly recorded in Book No..... of..... Records of..... County, Arizona, at pages.....

WITNESS my hand and official seal the day and year first above written.

..... County Recorder.

AMENDED
Notice of Location.

LODE CLAIM.

.....

Dated..... 190.....

Filed and recorded at the request of

.....

A. D., 190.....

at..... M.


Book.....

Page.....

County Recorder.

By.....

Deputy Recorder.



This diagram is to give locator a general idea of plan of location under the new law. The Discovery Shaft can be in the center of claim or any distance from either end desired. In the diagram it is placed 500 feet from one end and 1000 feet from the other. Commence description of claim at a center end monument, giving its distance and direction from center of Discovery Shaft; thence bound the claim in either direction. In description be careful to state locality of claim with reference to some natural object, or permanent monument, as will identify the claim.

4-687.

SURVEYOR-GENERAL'S CERTIFICATE OF APPROVAL OF FIELD NOTES AND SURVEY OF MINING CLAIM.

Department of the Interior.

Office of U. S. Surveyor-General,

Phoenix, Arizona.

July, 18th, 1903.

I, U. S. Surveyor-General for Arizona.

do hereby certify that the foregoing and hereto attached Field Notes and Return of the Survey of the Mining Claim of Solomon Springs Copper Co., by H. C. H. Palmer, Authorized Agent.

known as the Paris and Promise

situate in Warren mining district, Cochise County, Arizona

in Section 31 and 32, Township No. 23 S., Range No. 25 E. - G. & S. R. B. & M., designated as Survey No. 1749

executed by Geo. G. Clark, U. S. Deputy Mineral Surveyor, July 7th - July 8th, 1903, under my instructions dated

July 2nd, 1903, have been critically examined and the necessary corrections and explanations made, and the said Field Notes and Return, and the Survey they describe, are hereby approved. A true copy of the copy of the location certificate filed by the applicant for survey is included in the field notes.

Handwritten signature of Hugh H. Price

U. S. Surveyor-General for Arizona.

Survey No. 1749

AMENDED

SCALE 1"=300'

