

MS

0

2

5

0

9

Copied 2-18-08.

H. S.I.

4-683.

MINERAL SURVEY No. 2509

LOT No.

Arizona Land District.

FIELD NOTES

OF THE SURVEY OF THE MINING CLAIM OF

J. T. Hood

KNOWN AS THE

Wedge

Warren Mining District,

Cochise County, Arizona

Section approx. 15, Township 23 S., Range 24 E., Unsurveyed

Surveyed under instructions dated December 28, 1907

by H. W. Jorgensen
U. S. Mineral Surveyor.

Claim located January 1, 1904

Survey commenced January 24, 1908

Survey completed January 25, 1908

6-822

Claimant's address, Bisbee, Arizona.

Claimant's attorneys, Neale & Sutter, Bisbee, Arizona.

Feet.

Survey No. 2509.

WEDGE

Beginning at Cor. No.-1, the S. W. Cor., identical with location corner, and with Cor. No. 4 Come By Chance lode, Survey No. 1643, a pine post 5 ft. long, 4 ins. sq. set 2 ft. in the ground in a mound of stones and scribed 4-1643-CBC, I add. to scribing 1-2509-WL, whence an X-BR-2509 chiseled on a sandstone boulder 6" X 8", 3 ins. above ground brs S. 30 deg. 25 mins. E. 86.46 ft., and an X-BP-2509 scribed on the E.-end of a switch tie on the E. P. & S. W. R. R. spur to Denn mine brs N. 69 deg. 45 mins. W. 100.10 ft. and U. S. M. M. No. 4 brs N. 71 deg. 51 mins. 30 secs. W. 4488.7 ft.

Thence N. 46 degs. 28 mins. E.

21.6 to intersection with S. side frame shack 10 x 14 ft. at 1.1 ft. from S. W. Cor.

28.1 same bearing to intersection with W. side frame shack at 6.4 ft from S. W. Cor.

142.8 same bear. to Cors. No. 3, 4 and 8 of the Come By Chance lode, Surv. No. 1643, Ophir lode, Surv. No. 1981 and Protection lode, Surv. No. 1985, respectively.

144.7 Same bear. to Cor. No. 2, the N. W., Cor., a corner of location, a pine post 4 ft. long 4 ins. sq. set 18 ins. in the ground in a mound of stones and scribed 2-2509-WL, whence a quartzite boulder 18" X 10" X 6" above ground chiseled 2-2509-BR, brs N. 0 degs. 07 mins. E. 13.38 ft.

Thence S. 54 degs. 12 mins. E.

16.8 to cor. No. 3, the N. E. Cor. identical with location and with Cor. No. 7 Protection lode, Survey No. 1985, a pine post 4 ft. long 4 ins. sq. set 18 ins. in the ground *(whence Cor. 8, Protection lode bears N. 60° 22' 04" 17.28 ft.,* in a mound of stones and scribed 3-2509-WL, whence a sandstone rock 12" X 12" X 4" above the surface chiseled X-BR-2509 brs N. 16 degs. 13 mins. E. 11.34 ft., and a quartzite rock 12" X 12" X 3" above the surface and chiseled the same brs S. 9 degs. 05 mins. W. 14.36 ft.

Thence S. 14 degs. 58 mins. W.

152.2 to Cor. No. 4 the S. E. Cor. identical with location, at

feet,

Survey No. 2509.

WEDGE (continued)

the intersection of line 6-7 Protection lode, Surv. No. 1985 and line 2-3 Erie Cattle Claim, Surv. No. 1464 at N. 14 degs. 58 mins. E 69.8 ft. from Cor. 6 Protection and N. 54 degs. 12 mins. W. 403.5 ft. from Cor. 3 Erie Cattle Claim, a pine post 4 ft. long, 4 ins. sq. set 18 ins. in the ground in a mound of stones and scribed 4-2509-WL, whence a sandstone boulder 6" X 8" X 3" above ground chiseled X-BR-2509 brs. S. 64 degs. 24 mins. W 38.82 ft. and the same chiseling on the concrete foundation, 12" X 12" X 6" above ground for the iron post at the S. W. Cor. of the Cemetery fence brs. S. 12 degs. 56 mins. W. 72.12 ft.

Thence N. 54 degs. 12 mins. W.

34. to orig. location for S. E. C.
97.7 same bearing to Cor. No. 1 the place of beginning.

Ledge

The presumed course of the ledge or vein on this claim is from the S. end center, N. 22 degs. 45 mins. E. 143.7 ft.

Area.

Total Area Wedge lode	0.187 A
Less area in conflict with Protection lode, Surv. No. 1985	<u>0.000 A</u>
Net area Wedge lode	0.187 A

Improvements

I hereby certify that the value of the labor and improvements on this claim, placed thereon by claimant or his grantor, is not less than \$500.00, and that said improvements consist of:

No. 1	Discovery Shaft 5 X 8 X 10 ft. deep brs from Cor. No. 1. S. 84 degs. 30 mins. E. 68 ft. value	\$100.00
No. 2	Shaft 4 X 6 X 48 ft. deep brs from Cor. No. 1, S. 72 degs. 40 mins. E. 79 ft., value	<u>\$500.00</u>
	Total improvements Wedge lode	\$600.00

Other improvements

One story frame cabin, 10 x 14 ft. facing W. the S. W. Cor. of which brs. from Cor. No. 1 N. 43 degs. 38 mins.

feet.

Survey No. 2509.

WEDGE (continued)

E. 21.8 ft.

One story frame cabin 12 X 16 ft. tent roof, facing W. the S. E. Cor. of which brs from Cor. No. 4. N. 0 degs. 45 mins. E. 60.8 ft.

One story frame cabin 12 x 16 ft. facing W., the N. E. Cor. of which brs from Cor. No. 3. S. 29 degs. 57 mins. W. 36.7 ft.

The owners of these cabins are unknown, and they are not claimed by the applicant herein.

Adjoining claims.

North and East, Protection lode, Surv. No. 1985, Superior and Pittsburg Mining Co., owners. Ophir lode, Survey No. 1951.

South Erie Cattle Claim, Surv. No. 1464, Superior & Pittsburg Mining Co., owner.

West Come By Chance, Surv. No. 1643, Denn Mining Co., owner.

Location.

This survey is located approximately in Sec. 15, T. 23, S, R. 24 E. G. & S. R. B. & M. Unsurveyed, in the Warren Mining District, Cochise County, Arizona.

Instruments

This survey was made with a Buff & Buff mining transit; the courses were deflected from the true meridian as determined by direct solar observation. The distances were measured with a 500 ft. and a 100 ft. steel tape.

Magnetic variation 12 degs. 30 mins. E.

Note:
The area in conflict with Protection lode, Survey No. 1985 is excluded from this survey.

Note:
The discrepancy in the bearing of line 2-3 Erie Cattle Claim, as shown in this survey^X and in the survey of Protection lode, Surv. No. 1985, is due to error in the latter survey.

Dated at Bisbee, Arizona, January 29, 1908.

H. M. Jorgensen.
U. S. Deputy Mineral Surveyor.

FINAL OATHS FOR SURVEYS.

LIST OF NAMES.

A list of the names of the individuals employed by H. W. Jorgensen
 United States Deputy Mineral Surveyor, to assist in running, measuring, and marking the lines, corners, and
 boundaries described in the foregoing field notes of the survey of the mining claim of
J. T. Hood
 known as the Wedge
 and showing the respective capacities in which they acted.

I. L. Wright, Chainman.
 _____, Chainman.
 _____, Axman.
 _____, Flagman.

FINAL OATHS OF ASSISTANTS.

I
~~We,~~ I. L. Wright
 and _____, do solemnly swear that I
~~we~~ assisted
H. W. Jorgensen, United States Deputy Mineral Surveyor, in marking the corners and surveying
 the boundaries of the mining claim of J. T. Hood
 known as the Wedge
 represented in the foregoing field notes as having been surveyed by said deputy mineral surveyor and under his
 direction; and that said survey has been in all respects, to the best of my
~~our~~ knowledge and belief, faithfully and
 correctly executed, and the corner and boundary monuments established according to law and the instructions
 furnished by the United States Surveyor-General for Arizona.

I. L. Wright, Chainman.
 _____, Chainman.
 _____, Axman.
 _____, Flagman.

Subscribed and sworn to by the above-named persons before me this 28th
 day of January, 1908.

*My commission
 expires Oct. 31 - 1911.*

Myrtle M. Gaus
 Notary Public.

FINAL OATH OF U. S. DEPUTY MINERAL SURVEYOR

I, H. W. Jorgensen, U. S. Deputy Mineral Surveyor, do solemnly swear that, in pursuance of instructions received from the United States Surveyor General for Arizona, dated December 28, 1907, I have, in strict conformity to the laws of the United States, the official regulations and instructions thereunder, and the instructions of said Surveyor General, faithfully and correctly executed the survey of the Mining Claim of J. T. Hood, known as the Wedge, situate in Warren Mining District, Cochise County, Arizona, in Section Approx. 15, Township No. 23 S., Range No. 24 E., Unsurveyed, and designated as Survey No. 2509, as represented in the foregoing field notes, which accurately show the boundaries of said mining claim as distinctly marked by monuments on the ground, and described in the attached copy of the location certificate, which was received by me from the Surveyor General with said instructions, and that all the corners of said survey have been established and perpetuated in strict accordance with the law, official regulations and instructions thereunder; and I do further solemnly swear that the foregoing are the true and original field notes of said survey and my report therein, and that the labor expended and improvements made upon said mining claim by claimant or his grantors are as therein fully stated, and that the character, extent, location and itemized value thereof are specified therein with particularity and full detail, and that no portion of said labor or improvements so credited to this claim has been included in the estimate of expenditures upon any other claim.

H. W. Jorgensen
U. S. Deputy Mineral Surveyor.

Subscribed and sworn to by the said H. W. Jorgensen, U. S. Deputy Mineral Surveyor, before me, Notary Public in and for the Cochise County, Ariz. this 28th day of January, 1908.

My Commission expires Oct. 21-1911. Marshall M. Galloway Notary Public.

Affidavit of Five Hundred Dollars Improvements.

We, John Cowan, and I. L. Wright

of lawful age, being first duly sworn according to law, depose and say: That we are acquainted with the Wedge mining claim, situate in Warren Mining district, Cochise County, Arizona Territory, for which J. T. Hood

has made application for survey prior to application for patent under the provisions of the act of Congress, approved May 10, 1872; and that the labor done and improvements made thereon by the applicant and his grantor exceed Five Hundred Dollars in value, and further that we are not personally interested in said mine.

John Cowan

I. L. Wright

TERRITORY OF ARIZONA, } ss:
County of COCHISE

Sworn to and subscribed before me, this 7th day of March, 1908



142965400-8-04 My commission expires Oct. 31-1911.

Notary Public

Notice of Mining Location

LODE CLAIM

To All Whom It May Concern:

This Mining Claim, the name of which is the WEDGE
Mining Claim, situate on lands belonging to the United States of America, and in which there
are valuable mineral deposits, was entered upon and located for the purposes of exploration and
purchase by Fred Kenney

a citizen of the United States
(Locator must insert either "a citizen of the United States," or, "who has declared his intention to become a citizen of the United States.")
the undersigned, on the 1st day of January 1904.

The length of this claim is 300 feet,
and I claim 160 feet,
in a Southerly direction and 89
feet in a Northerly direction from
the center of the discovery shaft, at which this notice is posted, lengthwise of the claim, together
with 90 feet in width of the surface grounds, on each
side of the center of said claim. The general course of the lode deposit and premises is from the
North to the South

The claim is situated and located in the Warren Mining District, in
Cochise County, in the Territory of Arizona, about one & one half
miles in an Easterly direction from the City of Bisbee. Said claim
joining cemetery on its west side

The surface boundaries of the claim are marked upon the ground as follows: Beginning at
a monument post

at a point in a ina Southerly direction 40 feet from
the discovery shaft (at which this notice is posted), being in the center of the South
end line of said claim; thence 40 feet to a pine Post
, being the South East corner of said claim; thence
Northerly 160 feet to a pine Post, being at the
North East corner of said claim; thence Westerly 40 feet
to a pine Post at the center of the North end of said claim;
thence Westerly 40 feet to a Pine Post, being at the
North west corner of said claim; thence Southerly 160
feet to a Pine post at the South West corner of said claim;
thence Easterly 40 feet to the place of beginning.

All done under the provisions of Chapter Six, of Title XXXII, of the Revised Statutes of
the United States, and of an Act of the General Assembly of Arizona, entitled "An Act to
Revise and Codify the Laws of the Territory of Arizona," approved March 16, 1901.

Dated and posted on the ground this 1st day of January 1904 at
12 A.M.

Witness

Adolph Sorensen

Fred Kenney

Filed and recorded at request of
Kenney Bros. Mch. 24 1904 at 9 AM.

in Book 30, Record of Mins, at Page 323

TERRITORY OF ARIZONA,
 County of..... } ss.

I,....., County Recorder in and for the County and Territory aforesaid, do hereby certify that the within instrument was filed for record at.....o'clock,.....M., on this.....day of.....190..., and duly recorded in Book No..... of.....Records of.....County, Arizona, at pages.....

WITNESS my hand and official seal the day and year first above written.

.....
 County Recorder.

Notice of Location

LODE CLAIM

Dated.....190.....

Filed and Recorded at request of.....

.....
 A. D. 190.....

at.....M.


Book.....

Pages.....

.....
 County Recorder.

By.....
 Deputy Recorder.

THE H. H. McNEIL CO., PRINTERS, PHOENIX, ARIZONA.



This diagram is to give locator a general idea of plan of location under the new law. The Discovery Shaft can be in the center of claim or any distance from either end desired. In the diagram it is placed 500 feet from one end and 1000 feet from the other. Commence description of claim at a center end monument, giving its distance and direction from center of Discovery Shaft; thence bound the claim in either direction. In description be careful to state locality of claim with reference to some natural object, or permanent monument, as will identify the claim.

U. S. SURVEYOR GENERAL'S FINAL CERTIFICATE ON
FIELD NOTES.

DEPARTMENT OF THE INTERIOR,

OFFICE OF U. S. SURVEYOR GENERAL,

Phoenix, Arizona

April 7, 1908.

I, U. S. Surveyor General for District of Arizona,
do hereby certify that the foregoing transcript of the Field Notes, return and approval
of the Survey of the mining claim of

J. T. Hood

, known as the WEDGE

, situate in Warren

Mining District, Cochise County,

Arizona, in Section approx. 15, Township No. 23 S,

Range No. 24 E. Unsur., and designated as Survey

No. 2509, has been correctly copied from the originals on

file in this office; that said Field Notes furnish such an accurate description of said
mining claim as will, if incorporated into a patent, serve fully to identify the premises,
and that such reference is made therein to natural objects or permanent monuments as
will perpetuate and fix the locus thereof.

And I further certify that five hundred dollars' worth of labor has been expended
or improvements made upon said mining claim by claimant or his grantors, and
that said improvements consist of 2 shafts, value \$600.00

and that no portion of said labor or improvements has been included in the estimate of
expenditures upon any other claim.

I further certify that the plat thereof, filed in the U. S. Land Office at Phoenix,
Arizona is correct and in conformity with the foregoing Field Notes.

Frank S. Ingalls

United States Surveyor General for Arizona.

TERRITORY OF ARIZONA, |
| SS.
COUNTY OF COCHISE. |

I, C. A. McDonald, County Recorder in and for said County, hereby certify that I have compared the annexed and foregoing copy with the original Location Notice of the WEDGE mining claim, filed for record in my office on the 24th day of March A.D. 1904, and recorded in Book 30, Record of Mines, at Page 323, and that the same is a full, true and correct copy of said original and of the whole thereof.

WITNESS MY HAND AND SEAL of office, this 16th day of November, A.D. 1907.

C. A. McDonald

COUNTY RECORDER.

4-687.

SURVEYOR-GENERAL'S CERTIFICATE OF APPROVAL OF FIELD NOTES AND SURVEY OF MINING CLAIM.

Department of the Interior,

Office of U. S. Surveyor-General,

Phoenix, Arizona

April 7, 1908.

I, U. S. Surveyor-General for District of Arizona

do hereby certify that the foregoing and hereto attached Field Notes and Return of the Survey of the Mining Claim of

J. T. Hood

, known as the

WEDGE

situate in Warren Mining District,

Cochise County, Arizona

in Section approx. 15, Township No. 23 S., Range No. 24 E., Unsur.

, designated as Survey No. 2509

executed by H. W. Jorgensen, U. S. Deputy Mineral

Surveyor, January 24, - 25, 1908, under my instructions dated

December, 28, 1907, have been critically examined and the necessary

corrections and explanations made, and the said Field Notes and Return, and the Survey they describe,

are hereby approved. A true copy of the copy of the location certificate filed by the applicant for

survey is included in the field notes.

Frank Singer


U. S. Surveyor-General for Arizona.

SURVEY NO. 2509

Scale: 1" = 50'



This map shows the location of the cabin and the location of the cabin on the map.



This map shows the location of the cabin and the location of the cabin on the map.

Large
Map