

JUL 31 1911

4-683.

MINERAL SURVEY No. 2927.

LOT No.

Arizona Land District.

FIELD NOTES

OF THE SURVEY OF THE MINING CLAIM OF

Arizota Mining Company

KNOWN AS THE

Cottonwood Pass

Ellsworth Mining District,

Yuma County, Arizona.

Approx. Sections 32 & 34, Townships 6 & 7 N., Range 14 W., G&S.R.M., Uns.

Surveyed under instructions dated May 22, 1911.

by C. C. Thompson,
U. S. Mineral Surveyor.

Claim located See Location Notice, 1910.

Survey commenced June 20, 1911.

Survey completed June 20, 1911.

6-822

Address of claimant's Attorney:

Chambers Kellar,
Lead City,
South Dakota.

SURVEY NO. 2927.

COTTONWOOD PASS LODE.

Beginning at Cor. No. 1.

Identical with the N. W. Cor. Good Hope lode, unsurveyed, belonging to the claimant herein.

An andesitic rock, 10 x 14 x 26 ins., set 14 ins. in the ground, with mound of stone, chiseled a cross (x) at the exact Cor. point and 1-C-2927, whence,

The U. S. M. M. No. 2927, bears N. 47° 56' E. 386.2 ft.

No other bearings available.

Feet.
300.
600

Thence S. 55° 55' W.
To N.C.E., a stone monument 3 ft. high.
To Cor. No. 2.

A schistose rock, 6 x 10 x 24 ins., set 12 ins. in the ground, with mound of stone, chiseled a cross (x) at the exact Cor. point and 2-C-2927. No bearings available.

485
1500

Thence S. 36° 35' E.
Middle of a dry drain, 20 ft. wide, flows N. 80° W.
To Cor. No. 3.

Identical with the N. W. Cor. Snapp lode, unsurveyed, belonging to the claimant herein.

A schistose rock, 5 x 12 x 24 ins., set 12 ins. in the ground, with mound of stone, chiseled a cross (x) at the exact Cor. Point and 3-C-2927. No bearings available.

300.
600

Thence N. 55° 55' E.
To S.C.E., a stone monument 3 ft. high.
To Cor. No. 4.

Identical with the N. E. Cor. Snapp lode, unsurveyed. Also identical with the S. W. Cor. Good Hope lode, unsurveyed.

A schistose rock, 4 x 8 x 26 ins., set 14 ins. in the ground, with mound of stone, chiseled a cross (x) at the exact Cor. point and 4-C-2927. No bearings available.

SURVEY NO. 2927.

Feet. Thence N. 36° 35' W.
 620 Middle of a dry drain, 20 ft. wide, flows westerly.
 1500 To Cor. No. 1, the place of beginning.

Lode Line.

As near as can be determined from present develop-
ments the lode line of this claim extends from its
discovery point as follows: S. 36° 35' E. 450 ft. and
N. 36° 35' W. 1050 ft. -----

All corners of this survey are identical with the
corners of the amended location.

Variation at all corners 14° E.

AREA.

Total area Cottonwood Pass lode 20.641 Acres.

LOCATION.

This claim is located approximately in Secs. 3 & 34, T_s. 6 & 7 N.,
Uns.,
R. 14 W., G.&S. R. M, in the Ellsworth Mining District,
Yuma County, Arizona.

EXPENDITURE OF FIVE HUNDRED DOLLARS.

I certify that the value of the labor and improve-
ments made upon this claim by the claimant or its
grantors is not less than five hundred dollars, and
that said improvements consist of:

- No. 1 The discovery cut, the face of which is on the center
line 440 ft. from center of line 3-4, 4 ft. wide, 8 ft.
face, running N. 36° 35' W. 10 ft. to discovery point,
thence N. 25° W. 25 ft. to mouth. Value, \$300.00
- No. 2 A shaft which bears from Cor. No. 4, N. 66° 30' W.
585 ft., 4 x 6 x 10 ft. deep. Value, \$100.00
- No. 3 A shaft which bears from Cor. No. 1, S. 3° 45' E.
342 ft., 4 x 7 x 7 ft. deep. Value, \$70.00

SURVEY NO. 2927.

No. 4 A shaft which bears from Cor. No. 1, S. 41° 30' W. 270 ft., 4 x 7 x 22 ft. deep.

Value, \$220.00

OTHER IMPROVEMENTS.

Cottonwood Spring which bears from Cor. No. 1, S. 31° 33' E. 833 ft., a cylindrical shaft lined with rock 10 ft. deep. The spring is inclosed in a wooden box and water is drawn by means of rope and bucket. It belongs to claimant herein.

INSTRUMENT.

This survey was made with a C. L. Berger & Sons No. 4 transit. The courses were deflected from a true Meridian established by observing Polaris at eastern elongation. The distances were measured with a 660 ft. Lufkin steel tape.

REPORT.

U. S. M. M. No. 2927 is a rock in place 3 x 5 ft., showing 2 ft. above ground, with mound of stone, chiselled a cross (x) and U. S. M. M. No. 2927.

ADJOINING CLAIMS.

This survey is joined on the N. E. by the Good Hope lode, and on the S. E. by the Snapp lode, both unsurveyed and claimed by claimant herein.

U. S. MINERAL MONUMENT NO. 2927.

In my Sur. No. 2927, Cottonwood Pass lode, it became necessary to establish a new U. S. Mineral Monument for the reason that no such monument or other Cor. of the Public Surveys exists within a radius of two miles of the said claim.

Upon a high point, visible in all directions, I selected a rock in place, showing 3 x 5 ft. x 2 ft. above ground, chiseled U. S. M. M. No. 2927 and a cross (x) at the exact point, whence

A cross (x) on a rock in place, 3 x 6 x 2 ft. above ground, chiseled B. R. U. S. M. M. No. 2927, bears S. 11° 30' W. 36.7 ft.

A cross (x) on a rock in place, 5 x 7 x 8 ft. above ground, chiseled B. R. U. S. M. M. No. 2927, bears N. 69° 00' W. 29.2 ft.

Cottonwood Spring bears S. 8° 45' E. 980 ft.

Planet Peak bears N. 42° 57' W.

The Town of Wenden bears S. 59° E. about 10 miles.

This monument is located in the Ellsworth Mining District, Yuma County, Arizona, approximately in T. 6 N., R. 14 W., G. & S. R. M. and a monument of stone 6 ft. diam. and 6 ft. high is built alongside.

C. L. Thompson,
U. S. Mineral Surveyor.

FINAL OATHS FOR SURVEYS.

LIST OF NAMES.

A list of the names of the individuals employed by C. C. Thompson

United States Mineral Surveyor, to assist in running, measuring, and marking the lines, corners, and boundaries described in the foregoing field notes of the survey of the mining claim of

Arizota Mining Company

known as the Cottonwood Pass

and showing the respective capacities in which they acted.

J. A. Hickey, Chainman.

Chainman.

Arman.

Flagman.

FINAL OATHS OF ASSISTANTS.

We, I, J. A. Hickey

~~and~~ do solemnly swear that ^I ~~we~~ assisted

C. C. Thompson, United States Mineral Surveyor, in marking the corners and surveying

the boundaries of the mining claim of Arizota Mining Company

known as the Cottonwood Pass

represented in the foregoing field notes as having been surveyed by said mineral surveyor and under his direction; and that said survey has been in all respects, to the best of our knowledge and belief, faithfully and correctly executed, and the corner and boundary monuments established according to law and the instructions furnished by the United States Surveyor-General for Arizona.

J. A. Hickey, Chainman.

Chainman.

Arman.

Flagman.

Subscribed and sworn to by the above-named persons before me this 30th

day of Jan, 1911

My commission expires Jan. 11, 1915.

R. D. W. [Signature]
Notary Public

FINAL OATH OF U. S. MINERAL SURVEYOR.

I, C. C. Thompson, U. S. Mineral Surveyor, do solemnly swear that, in pursuance of instructions received from the United States Surveyor General for Arizona, dated May 23, 1911, I have, in strict conformity to the laws of the United States, the official regulations and instructions thereunder, and the instructions of said Surveyor General, faithfully and correctly executed the survey of the Mining Claim of Arizota Mining Company, known as the Cottonwood Pass, situate in Ellsworth Mining District, Yuma County, Arizona, approx., in Sections 3 and 34, Townships Nos. 6 & 7 N., Range No. 14 W., G. & S. R. M., Uns., and designated as Survey No. 2927, as represented in the foregoing field notes, which accurately show the boundaries of said mining claim as distinctly marked by monuments on the ground, and described in the attached copy of the location certificate, which was received by me from the Surveyor General with said instructions, and that all the corners of said survey have been established and perpetuated in strict accordance with the law, official regulations and instructions thereunder; and I do further solemnly swear that the foregoing are the true and original field notes of said survey and my report therein, and that the labor expended and improvements made upon said mining claim by claimant or its grantors are as therein fully stated, and that the character, extent, location, and itemized value thereof are specified therein with particularity and full detail, and that no portion of said labor or improvements so credited to this claim has been included in the estimate of expenditures upon any other claim.

C. C. Thompson
U. S. Mineral Surveyor.

Subscribed and sworn to by the said
U. S. Mineral Surveyor, before me
day of June, 1911

C. C. Thompson
Robert P. Kelly
John A. Kelly
this 30th
Robert P. Kelly
John A. Kelly

My commission expires Jan. 11, 1915.

2241

NOTICE OF MINING LOCATION

LODE CLAIM

JUN 12 1911

TO ALL WHOM IT MAY CONCERN :

This Mining Claim, the name of which is the Cottonwood Pass mining Claim, situate on lands belonging to the United States of America, and in which there are valuable mineral deposits, was entered upon and located for the purpose of exploration and purchase by James Snapp and Jos Whitehouse citizens of the United States, the under - signed, on the 5 day of April, 1910 .

The length of this claim is 1500 feet and we claim 450 feet in a S. 36° 30' E. direction and 1050 feet in a N. 36° 30' W. direction from the center of the discovery shaft, at which this notice is posted, lengthwise of the claim, together with 300 feet in width of the surface grounds, on each side of the center of said claim, . The general course of the lode deposit and premises is from the Southeasterly to the Northwesterly .

The claim is situated and located in the Ellsworth mining District in Yuma County, in the Territory of Arizona,

From its discovery shaft Cottonwood Springs bears N. 8° E. 300 ft. Its S.E. Cor. is identical with the S.W. Cor Good Hope lode .

The surface boundaries of the claim are marked upon the ground as follows : Beginning at a Monument at a point in a S. 36° 30' E. direction 450 feet from the discovery shaft (at which this notice is posted) being in the center of the South end line of said claim ; thence S. 56° W. 300 feet to a Monument , being the S.W. corner of said claim ; thence N. 36° 30' W. 1500 feet to a Monument , being at the N.W. corner of said claim; thence N. 56° E. 300 feet to a Monument at the center of

North end of said claim; thence N. 56 E. 300 feet to a Monument , being at the N.E. corner of said claim ; thence S. 36 30 E. 1500 feet to a Monument at the S.E. corner of said claim ; thence S. 56 W. 300 feet to the place of beginning

Variation 14 E.

All done under the provisions of Chapter Six, of Title XXXII. of the Revised Statutes of the United States , and an Act of the General Assembly of Arizona, entitled " An Act to Revise and Codify the Laws of the Territory of Arizona ," approved March 16,1901 .

This is an Amended Location notice of the Cottonwood Pass Mining Claim, located by James Snapp and Jos Whitehouse on the 1 day of January 1910, and recorded in Book 5 of Records of Mines at page 48 in the office of the County Recorder of the aforesaid County of Yuma to which reference is hereby made and this Amended Location Notice is made and posted to correct errors in the description in the said original Location Notice .

Dated and posted on the ground this 5 day of April ,1910

James Snapp
Jos Whitehouse .


Filed and recorded at the request of Chambers Kellar Jun 23 ,A.D. 1910 at 9:24 oclock A.M.

J.M. Polhamus ,
County Recorder .

TERRITORY OF ARIZONA)
) ss.
COUNTY OF YUMA .)

I, J.M. Polhamus, County Recorder in and for the County of Yuma, Territory of Arizona, do hereby certify that the foregoing is a true , full and correct copy of the Cottonwood Pass Mining Claim as filed for record in my office on the 23rd day of June A.D. 1910 and which appears of record in Book 6 of Mines at Page 139 ,et seq ., records of County and Territory aforesaid .

In Witness Whereof I have hereunto set my hand and affixed my seal of office this 9th day of June A.D. 1911.


County Recorder Yuma County .

U. S. SURVEYOR-GENERAL'S FINAL CERTIFICATE ON FIELD NOTES.

Department of the Interior,

OFFICE OF U. S. SURVEYOR-GENERAL,

Phoenix, Arizona,

August 26, 1911.

I, U. S. Surveyor-General for Arizona, do hereby certify that the foregoing transcript of the Field Notes, return and approval of the survey of the mining claim of

Arizota Mining Company, known as the COTTONWOOD PASS,

situate in Ellsworth

Mining District, Yuma County, Arizona, approximately

in Section 3 and 34, Township Nos. 6 & 7 N., Range No. 14 W., G. & S. R. M. Uns and designated as Survey No. 2927,

has been correctly copied from the originals on file in this office; that said Field Notes furnish such an accurate description of said mining claim as will, if incorporated into a patent, serve fully to identify the premises, and that such reference is made therein to natural objects or permanent monuments as will perpetuate and fix the locus thereof.

And I further certify that five hundred dollars' worth of labor has been expended or improvements made upon said mining claim by claimant or its grantors, and that said improvements consist of 1 cut and 3 shafts, total value \$690.00

and that no portion of said labor or improvements has been included in the estimate of expenditures upon any other claim.

I further certify that the plat thereof, filed in the U. S. Land Office at Phoenix, Arizona, is correct and in conformity with the foregoing Field Notes.

Frank S. Ingalls,

United States Surveyor-General for Arizona,

SURVEYOR-GENERAL'S CERTIFICATE OF APPROVAL OF FIELD NOTES AND SURVEY OF MINING CLAIM.

Department of the Interior,

OFFICE OF U. S. SURVEYOR-GENERAL,

Phoenix, Arizona,

August 26, 1911.

I, U. S. Surveyor-General for Arizona,

do hereby certify that the foregoing and hereto attached Field Notes and Return of the Survey of the Mining Claim of

Arizota Mining Company,

known as the

COTTONWOOD PASS,

situate in Ellsworth mining district,

Yuma County, Arizona, approximately

in Section s 3 and 34, Township Nos 6 & 7., N., Range No. 14 W., G. S. R. M., Uns.

designated as Survey No. 2927,

executed by C. C. Thompson, United States Mineral

Surveyor, June 20, 1911, under my instructions dated

May 22, 1911, have been critically examined and the necessary cor-

rections and explanations made, and the said Field Notes and Return, and the Survey they describe,

are hereby approved. A true copy of the copy of the location certificate filed by the applicant for

survey is included in the field notes.

Handwritten signature of Frank S. Sigall

U. S. Surveyor-General for Arizona,